		DEPARTMENT	ATE OF UTAH OF NATURAL RES F OIL, GAS AND I				FOF	RM 3			
APPLI	CATION FOR F	PERMIT TO DRILL				1. WELL NAME and Greater	<b>I NUMBER</b> Monument Butte W-	7-9-17			
2. TYPE OF WORK  DRILL NEW WELL	REENTER P&A	WELL DEEPE	N WELL			3. FIELD OR WILDCAT MONUMENT BUTTE					
4. TYPE OF WELL Oil We	ell Coalbed	d Methane Well: NO				5. UNIT or COMMUNITIZATION AGREEMENT NAME GMBU (GRRV)					
6. NAME OF OPERATOR		7. OPERATOR PHO	ONE 435 646-4825								
8. ADDRESS OF OPERATOR		9. OPERATOR E-M	AIL crozier@newfield.cor	m							
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE)	t 3 Box 3630 , My	11. MINERAL OWNE		FEE (	_	12. SURFACE OWN					
UTU-72106  13. NAME OF SURFACE OWNER (if box 12	= 'fee')	110		J,			IER PHONE (if box				
15. ADDRESS OF SURFACE OWNER (if box	12 = 'fee')					16. SURFACE OWN	IER E-MAIL (if box	12 = 'fee')			
		10 THIFND TO COM	MANCHE PROPUE	TON FROM		19. SLANT					
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')		18. INTEND TO COM MULTIPLE FORMATI  YES (Submit Co			_		RECTIONAL 📵 🕒	IORIZONTAL 🗍			
20. LOCATION OF WELL	FOO	TAGES	QTR-QTR	SECTI	ION	TOWNSHIP	RANGE	MERIDIAN			
LOCATION AT SURFACE	691 FNL	2054 FWL	NENW	18		9.0 S	17.0 E	S			
Top of Uppermost Producing Zone	73 FNL	2511 FWL	NENW	NENW 18		9.0 S	17.0 E	S			
At Total Depth	175 FSL	2447 FEL	SWSE	7		9.0 S	17.0 E	S			
21. COUNTY  DUCHESNE		22. DISTANCE TO N	EAREST LEASE LIN	IE (Feet)		23. NUMBER OF A	CRES IN DRILLING	UNIT			
		25. DISTANCE TO NE (Applied For Drilling									
27. ELEVATION - GROUND LEVEL		28. BOND NUMBER				29. SOURCE OF DE	RILLING WATER / PPROVAL NUMBER	TE ADDITION DI E			
5440			WYB000493			WATER RIGHTS AI	437478	IF APPLICABLE			
		АТ	TACHMENTS								
VERIFY THE FOLLOWING	ARE ATTACHE	D IN ACCORDANG	CE WITH THE U	TAH OIL	AND (	GAS CONSERVAT	ION GENERAL R	ULES			
WELL PLAT OR MAP PREPARED BY	LICENSED SURV	EYOR OR ENGINEER	COM	IPLETE DRI	ILLING	i PLAN					
AFFIDAVIT OF STATUS OF SURFACE	OWNER AGREE	MENT (IF FEE SURF	ACE) FORI	FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER							
DIRECTIONAL SURVEY PLAN (IF DI	RECTIONALLY O	R HORIZONTALLY	г торо	TOPOGRAPHICAL MAP							
NAME Mandie Crozier		TITLE Regulatory T	ech	PHONE 435 646-4825							
SIGNATURE		<b>DATE</b> 11/30/2010		EMAIL mcrozier@newfield.com							
<b>API NUMBER ASSIGNED</b> 43013505130000		APPROVAL			B	acylll					
					p,	ermit Manager					

API Well No: 43013505130000 Received: 11/30/2010

	Proposed Hole, Casing, and Cement										
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)							
Prod	7.875	5.5	0	6115							
Pipe	Grade	Length	Weight								
	Grade J-55 LT&C	6115	15.5								

API Well No: 43013505130000 Received: 11/30/2010

	Proposed Hole, Casing, and Cement										
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)							
Surf	12.25	8.625	0	300							
Pipe	Grade	Length	Weight								
	Grade J-55 ST&C	300	24.0		П	Γ					

#### NEWFIELD PRODUCTION COMPANY GREATER MONUMENT BUTTE W-7-9-17 AT SURFACE: NE/NW SECTION 18, T9S, R17E DUCHESNE COUNTY, UTAH

#### TEN POINT DRILLING PROGRAM

#### 1. GEOLOGIC SURFACE FORMATION:

Uinta formation of Upper Eocene Age

#### 2. <u>ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:</u>

Uinta	0, -	1360'
Green River		1360'
Wasatch		5920'
Proposed TD		6115'

#### 3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:

Green River Formation (Oil) 1360' – 5920'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

Location & Sampled Interval Date Sampled Flow Rate Temperature Hardness pН Water Classification (State of Utah) Dissolved Calcium (Ca) (mg/l) Dissolved Iron (Fe) (ug/l) Dissolved Sodium (Na) (mg/l) Dissolved Magnesium (Mg) (mg/l) Dissolved Carbonate (CO<sub>3</sub>) (mg/l) Dissolved Bicarbonate (NaHCO<sub>3</sub>) (mg/l) Dissolved Chloride (Cl) (mg/l) Dissolved Sulfate (SO<sub>4</sub>) (mg/l) Dissolved Total Solids (TDS) (mg/l)

#### 4. PROPOSED CASING PROGRAM

a. Casing Design: Greater Monument Butte W-7-9-17

Size	li li	Interval		Grade	Coupling	Design Factors			
Size	Тор	Bottom	Weight	Grade	Couping	Burst	Collapse	Tension	
Surface casing	01	2001	24.0	1.55	STC	2,950	1,370	244,000	
8-5/8"	0'	300'	24.0	J-55	510	17.53	14.35	33,89	
Prod casing		0.4451	45.5	1.55	1.70	4,810	4,040	217,000	
5-1/2"	0*	6,115'	15.5	J-55	LTC	2.47	2.08	2.29	

#### Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg
Pore pressure at surface casing shoe = 8.33 ppg
Pore pressure at prod casing shoe = 8.33 ppg
Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. Cementing Design: Greater Monument Butte W-7-9-17

Job	Fill	Description	Sacks ft <sup>3</sup>	OH Excess*	Weight (ppg)	Yield (ft³/sk)	
Curfees essing	300'	Class G w/ 2% CaCl	138	30%	15.8	1.17	
Surface casing	300	Class G W/ 276 CaCl	161	30 /0	13.0	3.01.7	
Prod casing	4.115'	Prem Lite II w/ 10% gel + 3%	284	30%	11.0	3.26	
Lead	4,115	KCI	927	30 /0	11.0	3.20	
Prod casing	2,000'	50/50 Poz w/ 2% gel + 3%	363	30%	14.3	1.24	
Tail	2,000	KCI	451	3070	14.5	1,27	

- \*Actual volume pumped will be 15% over the caliper log
- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
- Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

## 5. <u>MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL</u>:

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to Exhibit C for a diagram of BOP equipment that will be used on this well.

#### 6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

From surface to ±350 feet will be drilled with an air/mist system. The air rig is equipped with a 6 ½" blooie line that is straight run and securely anchored. The blooie line is used with a discharge less than 100 ft from the wellbore in order to minimize the well pad size. The blooie line is not equipped with an automatic igniter or continuous pilot light and the compressor is located less than 100 ft from the well bore due to the low possibility of combustion with the air dust mixture. The trailer mounted compressor (capacity of 2000 CFM) has a safety shut-off valve which is located 15 feet from the air rig. A truck with 70 bbls of water is on stand by to be used as kill fluid, if necessary. From about ±350 feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

#### 7. AUXILIARY SAFETY EQUIPMENT TO BE USED:

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

#### 8. TESTING, LOGGING AND CORING PROGRAMS:

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 300' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +-. A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.


#### 9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:


No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.


## 10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:


It is anticipated that the drilling operations will commence the first quarter of 2011, and take approximately seven (7) days from spud to rig release.

#### T9S, R17E, S.L.B.&M. NEWFIELD EXPLORATION COMPANY N89\*52'E - 78.57 (G.L.O.) Bottom N88°51'21"E of Hole 2632.23' (Meas.) WELL LOCATION, W-7-9-17, LOCATED N88°51'57"E - 2532.32' (Meas.) AS SHOWN IN THE NE 1/4 NW 1/4 OF 2600" 7/8 Rebar Brass Cap SECTION 18, T9S, R17E, S.L.B.&M. Brass Cap DUCHESNE COUNTY, UTAH. Center of (Meas., Pattern Lot 1 2054 2640.97 DRILLING of Hole WNDOW W.O1,95.00N *N01'11'* (G.L.O.) Lot 2 NORTH (G.L.O.) BAR SCALE 1910 Brass Cap NOTES: 1. Well footages are measured at right angles to the Section Lines. 1910 Brass Cap 2. Bearings are based on Global Positioning Satellite observations. WELL LOCATION: 3. The Center of Pattern footages Lot 3 are 25' FNL & 2600 FEL. W-7-9-172640.47 ELEV. EXIST. GRADED GROUND = 5440' THIS IS TO CERTIFY THATO PREPARED FROM FIELD OF ACTUAL MADE BY ME OR UNDER WY SUPPRESSION THE SAME ARE TRUE AND SORRECT TO OF MY KNOWLEDGE NO BEING 18937 NO1.01"54"W W.00.55'37"W Lot 4 1910 Proportioned Brass Cap Not Set N88°50'41"E - 2634.72' (Meas.) N88°50'44"E - 2546.32' (Meas.) TRI STATE LAND SURVEYING & CONSULTING N89\*51'E - 78.66 (G.L.O.) 180 NORTH VERNAL AVE. - VERNAL, UTAH 84078 = SECTION CORNERS LOCATED (435) 781-2501W-7-9-17DATE SURVEYED: SURVEYED BY: D.G. BASIS OF ELEV; Elevations are base on (Surface Location) NAD 83 08-09-10 LOCATION: an N.G.S. OPUS Correction. $LATITUDE = 40^{\circ} 02' 10.38''$ DATE DRAWN: DRAWN BY: F.T.M. LAT. 40°04'09.56" LONG. 110°00'43.28" 09-20-10 LONGITUDE = 110° 03' 03.63" REVISED: (Tristate Aluminum Cap) Elev. 5281.57' SCALE: 1" = 1000'










	nglellen	Wol	Melt Melt	2	п	54	•	4			2	R R	·+	i
Newfeld Wells	Stribce Spirit Dalling Walling on Completion Production Of Man	Proclacing San Wall Water Infection Wall Day bloke	Played & Abondoned Shirth White Source Well Water Dispused Main	Milection Stations  Intellegistres	В			. +:	41.5	# #	£	В	NEWFIELD	Exhibit A
New		100 Land 100 E.S.		M M	+1	-/	and Palmeter	*i**	2	2	£	5	N HOX	Ē
•	¥	£	7.	n	я	1		2	-7	2 4	E	2	1 -	-
		2	1	×	1				2 2 2	*2 n	92	R		
ŕ	1	v =	и	E.		1 114	ीं क क की । क क	d 4	2	- R		*		- P
	(Sec	*		R	15.	āej ej	1000	4 20 2 2 2 4 4 4 4 4 5 4	ન ન		4	1		
	e		£	2 /	SS-1		4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	्रिस चार्य इस चार्य	1+1 [+1 2	<u>.</u>	9	*	*	-
501		2			र के की क क के की क की में		4 1 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	1 22 20 27 2	· · ·	771.	2	Ħ	*	•
	2	5	z. q	2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	21	1.3	ના ના વર્ષ નાના વર્ષ	10. 10. 10. 10. 10. 10. 10. 10. 10. 10.	1	1 1 1 1 1	£	. A		
-			-4	ein ei ei dei e dei			Jes et 9	। सन् स्ट क्षा सन्दर्भ इस्त क्षा इस्त क्षा	4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	્રા કુત્રુ હું કુત્રુ હું કુત્રુ કુત્રુ કુત્રુ કુત્રુ	***	ž z	3	
<b>?</b> *(	1	2	n 4.			ी ने न न न भी न च		ាប់កស ក្រុង ក្រុងព្រះ		35 6 4 6 4 4 4	e. n	*		=
	9		2 - 2 - 2 - 2 - 2 - 2 - 2 - 2 - 2 - 2 -	131	761314 7 1913 7 1913	200 d	संस्था है। संस्था स		1 7 1		27	2		
*	(e):					1 4 1 4 1 4 1 4 1 4 1 4 1 4 1 4 1 4 1 4	0 /10	7.3	18 4 4 1 18 4 4 1 18 4 1 1	2 5 5 6 35 5 7 7 9	4 s	B	) <b>*</b> [	
		t	2 1 1 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	65.03	12 H		145°					8		1
		9	9 4 9 4 9 4	-5 t	14.44 4.44 4.44 4.44				+111	4 48 . 4 4 11 . 4 4 4 1 . 4 4 4 2 .	**************************************			-
		p	42 44 44 E	1 1 1 1 1 1 1 1 1 1 1 1 1	101 N	A STATE OF			ने नह भारत व			5	-	$\vdash$
~		3	R	4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4					1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	669 696 636.	1 • 5 · 1 - 3 - 4 3	×		-
	9	Š .	*****	19 4 4 19 4 2 4 2 4 1					73	19978.	n n	R		-
				II I	**	13 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	101 00 00 00 101 101 102 101	ANTA Exit	115	4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	1 4 s	3		1
•	•			***	### ## A			1 0 0 0 0 1 0 0 0 0 1 0 0 0 0 1 0 0 0 0	4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	1 2 7 2 9 9 9	S-R1	8	*	1
••	-	b.	£.	4) (5) (5) (5)	•2	W.		42 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	10 10 10 10 10 10 10 10 10 10 10 10 10 1	10 400	1-	g		
	e:	2		48 4	1	TOTAL STATE OF THE	100	200	1	44	S-Ri	£	۰	
-		2	*	n À	** <u>*</u>	\$ U.O	4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4		4747	2 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	44 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	*	1	
<b>N</b> ()	=	* 100 P	æ	٤	R K	88-R15	4 7 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	4 75 8 V	14714 14714 14714	4734	4 2 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	R		三十二:
•	9	* 12	2	a	8	/ .	\$ 100 mm	जनम् जनम्	424		4 6 4 6	z	- INCORE	**
,			z.	g	n	•		*	E STATE	137	* * 4 * 4 * 4 * 4 * 4 * 4 * 4 * 4 * 4 *		8	





## **NEWFIELD EXPLORATION**

USGS Myton SW (UT) SECTION 18 T9S R17E W-7-9-17

Wellbore #1

Plan: Design #1

# **Standard Planning Report**

29 November, 2010





## PayZone Directional Services, LLC.

Planning Report



Database: Company: Project: Site:

EDM 2003.21 Single User Db **NEWFIELD EXPLORATION** USGS Myton SW (UT)

SECTION 18 T9S R17E

Well: W-7-9-17 Wellbore #1 Wellbore: Design #1 Design:

Local Co-ordinate Reference:

**TVD Reference:** MD Reference: North Reference:

**Survey Calculation Method:** 

Well W-7-9-17

W-7-9-17 @ 5452.0ft (Original Well Elev) W-7-9-17 @ 5452.0ft (Original Well Elev)

Minimum Curvature

USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA **Project** 

Map System: Geo Datum:

US State Plane 1983

North American Datum 1983

System Datum:

Mean Sea Level

Map Zone:

Site

Utah Central Zone

SECTION 18 T9S R17E

Site Position: From:

Мар Position Uncertainty:

Northing: Easting: Slot Radius: 7,183,900.00ft 2,049,800.00ft

Latitude: Longitude: Grid Convergence:

40° 1' 56.921 N 110° 2' 16.332 W

0.94 "

Well W-7-9-17, SHL LAT: 40° 02' 10.38, LONG: -110° 03' 03.63

0.0 ft

**Well Position** 

+N/-S +E/-W

1,301.8 ft -3,700.3 ft

IGRF2010

Northing: Easting:

2010/09/15

7,185,201.75 ft 2,046,099.69 ft Latitude: Longitude:

40° 2' 10.380 N 110° 3' 3.630 W

**Position Uncertainty** 

0.0 ft

Wellhead Elevation:

5,452.0 ft

11.40

**Ground Level:** 

65.81

5,440.0 ft

52,342

Wellbore Wellbore #1 **Magnetics** Model Name Sample Date Declination Dip Angle Field Strength (°) (°) (nT)

Design

Design #1

**Audit Notes:** 

Version:

Phase:

**PROTOTYPE** 

Tie On Depth: +E/-W

0.0

**Vertical Section:** 

Depth From (TVD) (ft) 0.0

+N/-S (ft) 0.0

(ft) 0.0 Direction (°) 36.47

**Plan Sections** Measured Vertical Build Dogleg Turn Depth Inclination **Azimuth** Depth +N/-S +E/-W Rate Rate Rate TFO (ft) (ft) (°/100ft) (°/100ft) (°/100ft) (°) (ft) (ft) (°) (°) **Target** 0.0 0.00 0.00 0.0 0.0 0.0 0.00 0.00 0.00 0.00 600.0 0.00 0.00 600.0 0.0 0.0 0.00 0.00 0.00 0.00 1,423.6 12.35 36.47 71.1 1,417.2 52.6 1.50 1.50 0.00 36.47 4,937.7 12.35 36.47 4,850.0 675.7 499.5 0.00 0.00 0.00 0.00 W-7-9-17 TGT 6,115.0 12.35 36.47 6,000.0 878.3 649.2 0.00 0.00 0.00 0.00



## PayZone Directional Services, LLC.

Planning Report



Database: Company: Project: Site: EDM 2003.21 Single User Db NEWFIELD EXPLORATION USGS Myton SW (UT)

SECTION 18 T9S R17E

Well: W-7-9-17
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well W-7-9-17

W-7-9-17 @ 5452.0ft (Original Well Elev) W-7-9-17 @ 5452.0ft (Original Well Elev)

Grid

Minimum Curvature

nned Survey									
Measured Depth (ft)	inclination	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	1.50	36.47	700.0	1.1	0.8	1.3	1.50	1.50	0.00
800.0	3.00	36.47	799.9	4.2	3.1	5.2	1.50	1.50	0.00
900.0	4.50	36.47	899.7	9.5	7.0	11.8	1.50	1.50	0.00
1,000.0	6.00	36.47	999.3	16.8	12.4	20.9	1.50	1.50	0.00
1,100.0	7.50	36.47	1,098.6	26.3	19.4	32.7	1.50	1.50	0.00
1,200.0	9.00	36.47	1,197.5	37.8	28.0	47.0	1.50	1.50	0.00
1,300.0	10.50	36.47	1,296.1	51.4	38.0	64.0	1.50	1.50	0.00
1,400.0	12.00	36.47	1,394.2	67.1	49.6	83.5	1.50	1.50	0.00
						88.4		1.50	0.00
1,423.6	12.35	36.47	1,417.2	71.1	52.6		1.50		
1,500.0	12.35	36.47	1,491.9	84.3	62.3	104.8	0.00	0.00	0.00
1,600.0	12.35	36.47	1,589.5	101.5	75.0	126.2	0.00	0.00	0.00
1,700.0	12.35	36.47	1,687.2	118.7	87.7	147.6	0.00	0.00	0.00
1,800.0	12.35	36.47	1,784.9	135.9	100.4	169.0	0.00	0.00	0.00
1,900.0	12,35	36.47	1,882.6	153.1	113.2	190.4	0.00	0.00	0.00
2,000.0	12.35	36.47	1,980.3	170.3	125.9	211.8	0.00	0.00	0.00
2,100.0	12.35	36.47	2,078.0	187.5	138.6	233.2	0.00	0.00	0.00
2,200.0	12.35	36.47	2,175.7	204.7	151.3	254.6	0.00	0.00	0.00
2,300.0	12.35	36.47	2,273.3	221.9	164.0	276.0	0.00	0.00	0.00
2,400.0	12.35	36.47	2,371.0	239.1	176.7	297.3	0.00	0.00	0.00
2,500.0	12.35	36.47	2,468.7	256.3	189.5	318.7	0.00	0.00	0.00
2,600.0	12.35	36.47	2,566.4	273.5	202.2	340.1	0.00	0.00	0.00
2,700.0	12.35	36.47	2,664.1	290.7	214.9	361.5	0.00	0.00	0.00
2,800.0	12.35	36,47	2,761.8	307.9	227.6	382.9	0.00	0.00	0.00
·									
2,900.0	12.35	36,47	2,859.4	325.1	240.3	404.3	0.00	0.00	0.00
3,000.0	12.35	36.47	2,957.1	342.3	253.0	425.7	0.00	0.00	0.00
3,100.0	12.35	36.47	3,054.8	359.6	265.8	447.1	0.00	0.00	0.00
3,200.0	12.35	36.47	3,152.5	376.8	278.5	468.5	0.00	0.00	0.00
3,300.0	12.35	36.47	3,250.2	394.0	291.2	489.9	0.00	0.00	0.00
3,400.0	12.35	36.47	3,347.9	411.2	303.9	511.3	0.00	0.00	0.00
3,500.0	12.35	36.47	3,445.6	428.4	316.6	532.7	0.00	0.00	0.00
3,600.0	12.35	36.47	3,543.2	445.6	329.3	554.1	0.00	0.00	0.00
3,700.0	12.35	36.47	3,640.9	462.8	342.1	575.5	0.00	0.00	0.00
3,800.0	12.35	36.47	3,738.6	480.0	354.8	596.9	0.00	0.00	0.00
3,900.0	12.35	36.47	3,836.3	497.2	367.5	618.3	0.00	0.00	0.00
4,000.0	12.35	36.47	3,934.0	514.4	380.2	639.7	0.00	0.00	0.00
4,100.0	12.35	36.47	4,031.7	531.6	392.9	661.1	0.00	0.00	0.00
4,200.0	12.35	36.47	4,129.3	548.8	405.6	682.5	0.00	0.00	0.00
4,300.0	12.35	36.47	4,227.0	566.0	418.4	703.8	0.00	0.00	0.00
4,400.0	12.35	36.47	4,324.7	583.2	431.1	725.2	0.00	0.00	0.00
4,500.0	12.35	36.47	4,422.4	600.4	443.8	746.6	0.00	0.00	0.00
4,600.0	12.35	36.47	4,520.1	617.6	456.5	768.0	0.00	0.00	0.00
4,700.0	12.35	36.47	4,617.8	634.8	469.2	789.4	0.00	0.00	0.00
4,800.0	12.35	36.47	4,715.5	652.0	481.9	810.8	0.00	0.00	0.00
			•			832.2	0.00	0.00	0.00
4,900.0	12.35	36.47 36.47	4,813.1	669.2	494.7		0.00	0.00	0.00
4,937.7	12.35	30.47	4,850.0	675.7	499.5	840.3	0.00	0.00	0.00
W-7-9-17 T			4.010.0	000 -		050.0		0.00	0.00
5,000.0	12.35	36.47	4,910.8	686.5	507.4	853.6	0.00	0.00	0.00



## PayZone Directional Services, LLC.

Planning Report



Database: Company: Project:

EDM 2003.21 Single User Db NEWFIELD EXPLORATION USGS Myton SW (UT)

SECTION 18 T9S R17E

Well: Wellbore: Design:

Site:

W-7-9-17 Wellbore #1 Design #1

Local Co-ordinate Reference:

**TVD Reference:** MD Reference: North Reference:

**Survey Calculation Method:** 

Well W-7-9-17

W-7-9-17 @ 5452.0ft (Original Well Elev) W-7-9-17 @ 5452.0ft (Original Well Elev)

Grid

Minimum Curvature

Measured Depth (ft)	inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,100.0	12.35	36.47	5.008.5	703.7	520.1	875.0	0.00	0.00	0.00
5,200.0	12.35	36,47	5,106.2	720.9	532.8	896.4	0.00	0.00	0.00
5,300.0	12.35	36.47	5,203.9	738.1	545.5	917.8	0.00	0.00	0.00
5.400.0	12.35	36.47	5,301.6	755.3	558.2	939.2	0.00	0.00	0.00
5,500.0	12.35	36.47	5,399.2	772.5	571.0	960.6	0.00	0.00	0.00
5,600.0	12.35	36.47	5,496.9	789.7	583.7	982.0	0.00	0.00	0.00
5,700.0	12.35	36.47	5,594.6	806.9	596.4	1,003.4	0.00	0.00	0.00
5,800.0	12.35	36.47	5,692.3	824.1	609.1	1,024.8	0.00	0.00	0.00
5,900.0	12.35	36.47	5,790.0	841.3	621.8	1,046.2	0.00	0.00	0.00
6,000.0	12.35	36.47	5,887.7	858.5	634.6	1,067.6	0.00	0.00	0.00
6,100.0	12.35	36.47	5,985.4	875.7	647.3	1,089.0	0.00	0.00	0.00
6,115.0	12.35	36.47	6,000.0	878.3	649.2	1,092.2	0.00	0.00	0.00

Targets									
Target Name - hit/mlss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
W-7-9-17 TGT - plan hits target - Circle (radius 75	0.00	0.00	4,850.0	675.7	499.5	7,185,877.49	2,046,599.15	40° 2' 16.977 N	110° 2' 57.068 W



Project: USGS Myton SW (UT) Site: SECTION 18 T9S R17E


Well: W-7-9-17 Wellbore: Wellbore #1 Design: Design #1

KOP @ 600' DOGLEG RATE 1.5 DEG/100



Azimuths to Grid North True North: -0.93° Magnetic North: 10.47°

Magnetic Field Strength: 52341.7snT Dip Angle: 65.81° Date: 2010/09/15 Model: IGRF2010



## NEWFIELD PRODUCTION COMPANY GREATER MONUMENT BUTTE W-7-9-17 AT SURFACE: NE/NW SECTION 18, T9S, R17E DUCHESNE COUNTY, UTAH

#### **ONSHORE ORDER NO. 1**

### **MULTI-POINT SURFACE USE & OPERATIONS PLAN**

#### 1. EXISTING ROADS

See attached Topographic Map "A"

To reach Newfield Production Company well location site Greater Monument Butte W-7-9-17 located in the NE 1/4 NW 1/4 Section 18, T9S, R17E, Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40-1.4 miles  $\pm$  to the junction of this highway and UT State Hwy 53; proceed southeasterly -11.3 miles  $\pm$  to it's junction with an existing road to the southwest; proceed southwesterly -2.5 miles  $\pm$  to it's junction with an existing road to the northwest; proceed northwesterly -0.5 miles  $\pm$  to it's junction with an existing road to the southwest; proceed southwesterly -0.1 miles  $\pm$  to the existing 3-18-9-17 well location.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

#### 2. PLANNED ACCESS ROAD

There is no proposed access road for this location. The proposed well will be drilled directionaly off of the existing 3-18-9-17 well pad. See attached **Topographic Map "B"**.

There will be **no** culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

#### 3. LOCATION OF EXISTING WELLS

Refer to Exhibit "B".

#### 4. <u>LOCATION OF EXISTING AND/OR PROPOSED FACILITIES</u>

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

#### 5. LOCATION AND TYPE OF WATER SUPPLY

Newfield Production will transport water by truck from nearest water source as determined by a Newfield representative for the purpose of drilling the above mentioned well. The available water sources are as follows:

Johnson Water District Water Right: 43-10136

Maurice Harvey Pond Water Right: 47-1358

Neil Moon Pond

Water Right: 43-11787

Newfield Collector Well

Water Right: 41-1817 (A30414DVA, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

#### 6. SOURCE OF CONSTRUCTION MATERIALS

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

#### 7. METHODS FOR HANDLING WASTE DISPOSAL

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

#### 8. <u>ANCILLARY FACILITIES</u>

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

#### 9. <u>WELL SITE LAYOUT</u>

See attached Location Layout Sheet.

#### **Fencing Requirements**

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

#### 10. PLANS FOR RESTORATION OF SURFACE:

#### a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

#### b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

#### 11. <u>SURFACE OWNERSHIP</u> – Bureau of Land Management.

#### 12. OTHER ADDITIONAL INFORMATION

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. MOAC Report #10-216, 11/1/10. Paleontological Resource Survey prepared by, Wade E. Miller, 10/22/10. See attached report cover pages, Exhibit "D".

Newfield Production Company requests 458' of buried water line to be granted in Lease UTU-72106.

It is proposed that the disturbed area will be 60' wide to allow for construction of the proposed access road, a 10" or smaller gas gathering line, a 4" poly fuel gas line, a buried 10" steel water injection line, a buried 3" poly water return line, and a and a 14" surface flow line. The planned access road will consist of a 20' permanent running surface (10' either side of the centerline) crowned and ditched in order to handle any run-off from any precipitation events that are prevalent to this area. The maximum grade will be less than 8%. There will be no culverts required along this access road. There will be turnouts as needed along this road to allow for increases in potential traffic issues. There are no fences encountered along this proposed road. There will be no new gates or cattle guards required. All construction material for this access road will be borrowed material accumulated during construction of the access road.

Both the proposed surface gas and buried water lines will tie in to the existing pipeline infrastructure. **Refer to Topographic Map "C."** The proposed water pipelines will be buried in a 4-5' deep trench constructed with a trencher or backhoe for the length of the proposal. The equipment will run on the surface and not be flat bladed to minimize surface impacts to precious topsoil in these High Desert environments. If possible, all proposed surface gas pipelines will be installed on the same side of the road as existing gas lines. The construction phase of the planned access road, proposed gas lines and proposed water lines will last approximately (5) days.

In the event that the proposed well is converted to a water injection well, a Sundry Notice 3160-5 form will be applied for through the Bureau of Land Management field office.

For a ROW plan of development, please refer to the Greater Monument Butte Green River Development SOP and as well as the Castle Peak and Eight Mile Flat Reclamation and Weed Management Plan.

#### Water Disposal

After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.

#### **Additional Surface Stipulations**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

#### **Details of the On-Site Inspection**

The proposed Greater Monument Butte W-7-9-17 was on-sited on 10/6/10. The following were present; Tim Eaton (Newfield Production), Christine Cimiluca (Bureau of Land Management), and Janna Simonsen (Bureau of Land Management). Weather conditions were clear and ground cover was 100% open.

#### **Hazardous Material Declaration**

Newfield Production Company guarantees that during the drilling and completion of the Greater Monument Butte W-7-9-17, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986.

Newfield also guarantees that during the drilling and completion of the Greater Monument Butte W-7-9-17, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

#### 13. LESSEE'S OR OPERATOR'S REPRENSENTATIVE AND CERTIFICATION:

#### Representative

Name:

Tim Eaton

Address:

Newfield Production Company

Route 3, Box 3630 Myton, UT 84052

Telephone:

(435) 646-3721

#### Certification

Please be advised that NEWFIELD PRODUCTION COMPANY is considered to be the operator of well #W-7-9-17, Section 18, Township 9S, Range 17E: Lease UTU-72106 Duchesne County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by, Federal Bond #WYB000493.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

11/29/10


Date

Mandie Crozier


Regulatory Specialist Newfield Production Company

## 2-M SYSTEM

Blowout Prevention Equipment Systems



**EXHIBIT C** 





December 1, 2010

State of Utah, Division of Oil, Gas and Mining ATTN: Diana Mason P.O. Box 145801 Salt Lake City, UT 84114-5801

RE: Directional Drilling

**Greater Monument Butte W-7-9-17**Greater Monument Butte (Green River) Unit

Surface Hole:

T9S-R17E Section 18: NENW (UTU-72106)

691' FNL 2054' FWL

Bottom Hole:

T9S-R17E Section 7: SWSE (UTU-72106)

175' FSL 2447' FEL

Duchesne County, Utah

Dear Ms. Mason;

Pursuant to the filing by Newfield Production Company (NPC) of an Application for Permit to Drill the above referenced well dated 11/29/10, a copy of which is attached, and in accordance with Oil and Gas Conservation Rule R649-3-11, NPC hereby submits this letter as notice of our intention to directionally drill this well.

The surface hole and target locations of this well are both within the boundaries of the Greater Monument Butte Unit (UTU-87538X), of which Newfield certifies that it is the operator. Further, Newfield certifies that all lands within 460 feet of the entire directional well bore are within the Greater Monument Butte Unit.

NPC is permitting this well as a directional well in order to mitigate surface disturbance by utilizing preexiting roads and pipelines.

Should you have any questions or require further information, please contact the undersigned at 303-383-4197 or by email at sgillespie@newfield.com.

Sincerely,


Newfield Production Company


Shane Gillespie Land Associate


(Continued on page 2)

Form 3160-3 FORM APPROVED (August 2007) OMB No. 1004-0137 Expires July 31, 2010 UNITED STATES Lease Serial No. DEPARTMENT OF THE INTERIOR UTU-72106 BUREAU OF LAND MANAGEMENT If Indian, Allotee or Tribe Name APPLICATION FOR PERMIT TO DRILL OR REENTER 7 If Unit or CA Agreement, Name and No. **V** DRILL la. Type of work: REENTER Greater Monument Butte 8. Lease Name and Well No. lb. Type of Well: ✓ Oil Well Gas Well ✓ Single Zone Multiple Zone Greater Monument Butte W-7-9-17 Name of Operator 9. API Well No. Newfield Production Company 3b. Phone No. (include area code) 10 Field and Pool, or Exploratory 3a. Address Route #3 Box 3630, Myton UT 84052 (435) 646-3721 Monument Butte 4. Location of Well (Report location clearly and in accordance with any State requirements \*) 11. Sec., T. R. M. or Blk. and Survey or Area Sec. 18, T9S R17E NE/NW 691' FNL 2054' FWL Sec. 18, T9S R17E (UTU-72106) At surface At proposed prod. zone SW/SE 175' FSL 2447' FEL Sec. 7, T9S R17E (UTU-72106) 12. County or Parish 13. State 14. Distance in miles and direction from nearest town or post office\* UT Duchesne Approximately 15.8 miles southeast of Myton, UT 15. Distance from proposed\* 17 Spacing Unit dedicated to this well 16. No. of acres in lease location to nearest property or lease line, ft. Approx. 175' f/lse, NA' f/unit (Also to nearest drig. unit line, if any) 1,188.92 20 Acres 20 BLM/BIA Bond No. on file 18 Distance from proposed location\* to nearest well, drilling, completed, applied for, on this lease, ft. 19. Proposed Depth WYB000493 Approx. 1357' 6,115 Elevations (Show whether DF, KDB, RT, GL, etc.) 22 Approximate date work will start\* 23. Estimated duration 5440' GL (7) days from SPUD to rig release 24. Attachments The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form: 4. Bond to cover the operations unless covered by an existing bond on file (see 1. Well plat certified by a registered surveyor. Item 20 above). 2. A Drilling Plan. 3 A Surface Use Plan (if the location is on National Forest System Lands, the 5. Operator certification Such other site specific information and/or plans as may be required by the SUPO must be filed with the appropriate Forest Service Office). 25. Signature Name (Printed Typed) Mandie Crozier Title Regulatory Specialist Approved by (Signature) Name (Printed Typed) Date Office Title Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of approval, if any, are attached. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

\*(Instructions on page 2)







## **United States Department of the Interior**

## **BUREAU OF LAND MANAGEMENT**

Utah State Office P.O. Box 45155 Salt Lake City, Utah 84145-0155

IN REPLY REFER TO: 3160 (UT-922)

December 1, 2010

#### Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2010 Plan of Development Greater Monument

Butte Unit, Duchesne and Uintah Counties,

Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2010 within the Greater Monument Butte Unit, Duchesne and Uintah Counties, Utah.

BHL Sec 23 T08S R17E 2491 FSL 0146 FWL

API#	WELL NAME	LOCATI	ON
(Proposed PZ	GREEN RIVER)		
43-013-50511	~		9S R17E 0650 FSL 0640 FWL 9S R17E 1715 FSL 1718 FWL
43-013-50512			9S R17E 0642 FSL 0620 FWL 9S R17E 1481 FSL 0183 FEL
43-013-50513			9S R17E 0691 FNL 2054 FWL 9S R17E 0175 FSL 2447 FEL
43-013-50514			8S R17E 0645 FNL 0642 FWL 8S R17E 1474 FNL 1475 FWL
43-013-50515			8S R17E 1959 FNL 2011 FWL 8S R17E 2597 FSL 2309 FEL
43-013-50516			8S R17E 1975 FNL 1998 FWL 8S R17E 2568 FSL 1183 FWL
43-013-50517			8S R17E 2002 FNL 0635 FEL 8S R17E 1414 FNL 0278 FWL
43-013-50518	GMBU 0-23-8-17	Sec 22 T0	8S R17E 2017 FNL 0650 FEL

Page 2

API# WELL NAME LOCATION

(Proposed PZ GREEN RIVER)

43-013-50519 GMBU S-22-8-17 Sec 22 T08S R17E 0612 FSL 0499 FEL BHL Sec 22 T08S R17E 1438 FSL 1306 FEL

43-013-50520 GMBU P-23-8-17 Sec 22 T08S R17E 0618 FSL 0479 FEL BHL Sec 23 T08S R17E 1190 FSL 0376 FWL

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L. Coulthard

DN: cn-Michael L. Coulthard, o-Bureau of Land Management, ou-Branch of Minerals, email-Michael\_Coulthard@blm.gov, c-

bcc: File - Greater Monument Butte Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:12-1-10


## WORKSHEET APPLICATION FOR PERMIT TO DRILL

**APD RECEIVED:** 11/30/2010 **API NO. ASSIGNED:** 43013505130000 WELL NAME: Greater Monument Butte W-7-9-17 **OPERATOR:** NEWFIELD PRODUCTION COMPANY (N2695) **PHONE NUMBER:** 435 646-4825 **CONTACT:** Mandie Crozier PROPOSED LOCATION: NENW 18 090S 170E **Permit Tech Review:** SURFACE: 0691 FNL 2054 FWL **Engineering Review: BOTTOM:** 0175 FSL 2447 FEL Geology Review: **COUNTY: DUCHESNE LATITUDE: 40.03625 LONGITUDE:** -110.05028 UTM SURF EASTINGS: 581028.00 **NORTHINGS: 4432002.00** FIELD NAME: MONUMENT BUTTE LEASE TYPE: 1 - Federal **LEASE NUMBER: UTU-72106** PROPOSED PRODUCING FORMATION(S): GREEN RIVER SURFACE OWNER: 1 - Federal **COALBED METHANE: NO RECEIVED AND/OR REVIEWED: LOCATION AND SITING:** ✓ PLAT R649-2-3. Unit: GMBU (GRRV) Bond: FEDERAL - WYB000493 **Potash** R649-3-2. General Oil Shale 190-5 **Oil Shale 190-3** R649-3-3. Exception Oil Shale 190-13 **Drilling Unit** Board Cause No: Cause 213-11 Water Permit: 437478 **Effective Date:** 11/30/2009 **RDCC Review:** Siting: Suspends General Siting **Fee Surface Agreement Intent to Commingle** ✓ R649-3-11. Directional Drill **Commingling Approved** 

**Comments:** Presite Completed

**Stipulations:** 4 - Federal Approval - dmason

15 - Directional - dmason 27 - Other - bhill API Well No: 43013505130000



## State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

## Permit To Drill

\*\*\*\*\*\*

**Well Name:** Greater Monument Butte W-7-9-17

API Well Number: 43013505130000 Lease Number: UTU-72106 Surface Owner: FEDERAL

**Approval Date:** 12/6/2010

#### **Issued to:**

NEWFIELD PRODUCTION COMPANY, Rt 3 Box 3630, Myton, UT 84052

#### **Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 213-11. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

#### **Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

#### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

#### **Conditions of Approval:**

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Production casing cement shall be brought up to or above the top of the unitized interval for the Greater Monument Butte Unit (Cause No. 213-11).

#### **Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

• Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please leave a voicemail message if not available)
OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at https://oilgas.ogm.utah.gov

API Well No: 43013505130000

### **Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) due prior to implementation
- Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
- Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

**Approved By:** 

For John Rogers Associate Director, Oil & Gas Form 3160-3 (August 2007)

### UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM	APPRO	VED
OMB N	lo. 1004	0137
Expires	July 31,	2010

### 5. Lease Serial No. UTU-72106

APPLICATION FOR PERMIT TO	6. If Indian, Allotee or NA	Tribe Name				
la. Type of work:	7 If Unit or CA Agreement, Name and No. Greater Monument Butte					
lb. Type of Well:	Lease Name and Well     Greater Monument	7.7.7				
Name of Operator Newfield Production Company		· · · · · · · · · · · · · · · · · · ·	9. API Well No.	50513		
3a. Address Route #3 Box 3630, Myton UT 84052	3b. Phone No. (include area code (435) 646-3721	3)	10. Field and Pool, or Exp.  Monument Butte			
4. Location of Well (Report location clearly and in accordance with an	• •		11. Sec., T. R. M. or Blk.a			
At surface NE/NW 691' FNL 2054' FWL Sec. 18, T9			Sec. 18, T9S R17E	Ξ.		
At proposed prod. zone SW/SE 175' FSL 2447' FEL Sec.	7, T9S R17E (UTU-72106)					
<ol> <li>Distance in miles and direction from nearest town or post office*</li> <li>Approximately 15.8 miles southeast of Myton, UT</li> </ol>			12. County or Parish Duchesne	13. State UT		
Distance from proposed* location to nearest property or lease line, ft. Approx. 175' f/lse, NA' f/unit (Also to nearest drig. unit line, if any)	1			20 Acres		
8. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.  Approx. 1357'	19. Proposed Depth 6,115'		/BIA Bond No. on file NYB000493			
1. Elevations (Show whether DF, KDB, RT, GL, etc.) 5440' GL	22. Approximate date work will	22. Approximate date work will start*		Estimated duration     (7) days from SPUD to rig release		
	24. Attachments					
the following, completed in accordance with the requirements of Onshord.  Well plat certified by a registered surveyor.  A Drilling Plan.  A Surface Use Plan (if the location is on National Forest System SUPO must be filed with the appropriate Forest Service Office).	4. Bond to cover Item 20 above Lands, the 5. Operator cer	er the operation e). tification	is form:  ns unless covered by an exis  ormation and/or plans as may	<b>C</b>		
5. Signature Carrelio Crosses	Name (Printed/Typed) Mandie Crozier		Date	129/10		
Regulatory Specialist						
pproved by (Signature)	Name (Printed/Typed)  Jerry I	<b>Senczk</b>	<b>a</b> Dat	MAY 0 2 2011		
tile Asylistant Field Manager Lands & Mineral Resources	Office VERNAL F	TELD OF	FICE			
pplication approval does not warrant or certify that the applicant holds onduct operations thereon. Onditions of approval, if any, are attached the province of approval of the province o	s legal or equitable title to those r	ights in the sub APP	ect lease which would entitle	TACH		

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

**NOTICE OF APPROVAL** 

RECEIVED MAY 0 4 2011

DIV. OF OIL, GAS & MINING



BLM VERNAL, UTAH



# UNITED STATES DEPARTMENT OF THE INTERIOR **BUREAU OF LAND MANAGEMENT VERNAL FIELD OFFICE**

**VERNAL, UT 84078** 

(435) 781-440(



# CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company:	Newfield Production Company	Location:	NENW, Sec. 18, T9S, R17E (S)
			SWSE, Sec. 7, T9S, R17E (B)
Well No:	<b>Greater Monument Butte W-7-9-17</b>	Lease No:	UTU-72106
API No:	43-013-50513	Agreement:	Greater Monument Butte Unit

**OFFICE NUMBER:** 

170 South 500 East

(435) 781-4400

**OFFICE FAX NUMBER: (435) 781-3420** 

# A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR FIELD REPRESENTATIVE TO INSURE COMPLIANCE

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.

### **NOTIFICATION REQUIREMENTS**

Location Construction (Notify Environmental Scientist)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings to: ut vn opreport@blm.gov.
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	_	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

Page 2 of 7 Well: GMB W-7-9-17

5/3/2011

# SURFACE USE PROGRAM CONDITIONS OF APPROVAL (COAs)

- All new and replacement internal combustion gas field engines of less than or equal to 300 designrated horsepower must not emit more than 2 gms of NO<sub>x</sub> per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO<sub>x</sub> per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.

### **CONDITIONS OF APPROVAL:**

- Construction and drilling is not allowed from May 1<sup>st</sup> June 15<sup>th</sup> to minimize impacts during Mountain plover nesting.
- Construction and drilling is not allowed from March 1<sup>st</sup> August 31<sup>st</sup> to minimize impacts during burrowing owl nesting.
- If it is anticipated that construction or drilling will occur during the given timing restriction, a BLM or qualified biologist shall be notified so surveys can be conducted. Depending upon the results of the surveys, permission to proceed may or may not be recommended or granted by the BLM Authorized Officer.
- The reclamation seed mix will incorporate low growing grasses and not crested wheatgrass since this negatively impacts mountain plover habitat.
- Prior to any surface-disturbing activities between March 1<sup>st</sup> and August 31<sup>st</sup>, a BLM biologist or a BLM-approved contractor will survey all areas during April or May within a range of ½-mile from proposed surface disturbances for active raptor nests. If occupied/active raptor nests are found, construction will not occur during the nesting season for that species within its species-specific buffer.
- Hospital mufflers will be installed on new and existing pump jacks at the host well locations.
- Screening will be placed on stacks and on other openings of heater-treaters or fired vessels to prevent entry by migratory birds.

### Reclamation

• Reclamation will be completed in accordance with the Newfield Exploration Company Castle Peak and Eight Mile Flat Reclamation Plan on file with the Vernal Field Office of the BLM.

Page 3 of 7 Well: GMB W-7-9-17 5/3/2011

Appropriate erosion control and re-vegetation measures will be employed. In areas with unstable soils where
seeding alone may not adequately control erosion, grading will be used to minimize slopes and water bars will
be installed on disturbed slopes. Erosion control efforts will be monitored by Newfield and, if necessary,
modifications will be made to control erosion.

### **Seed Mix (Interim and Final Reclamation)**

Common Name	Latin Name	Pure Live Seed (lbs/acre)	Seed Planting Depth	
Squirreltail grass	Elymus elymoides	2.0	1/4 - 1/2"	
Needle and thread grass	Hesperostipa comata	2.0	1/2"	
Siberian Wheatgrass	Agropyron fragile	2.0	1/2"	
Shadscale saltbush	Atriplex confertifolia	2.0	1/2"	
Four-wing saltbush	Atriplex canescens	2.0	1/2"	
Gardner's saltbush	Atriplex gardneri	2.0	1/2"	
Blue flax (Lewis flax)	Linum lewisii	1.0	1/8 - 1/4"	

- All pounds are pure live seed.
- All seed and mulch will be certified weed free.
- Rates are set for drill seeding; double rate if broadcasting.

### **Monitoring and Reporting**

- The operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) that
  designates the proposed site-specific monitoring and reference sites chosen for the location. A
  description of the proposed sites shall be included, as well as a map showing the locations of the proposed
  sites.
- The operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) 3 growing seasons after reclamation efforts have occurred evaluating the status of the reclaimed areas in order to determine whether the BLM standards set forth in the Green River District Reclamation Guidelines have been met (30% or greater basal cover).

Page 4 of 7 Well: GMB W-7-9-17 5/3/2011

# DOWNHOLE PROGRAM CONDITIONS OF APPROVAL (COAs)

### SITE SPECIFIC DOWNHOLE COAs:

• The operator shall comply with all applicable requirements in the SOP (version: "Greater Monument Butte Green River Development Program", June 24, 2008). The operator shall also comply with applicable laws and regulations; with the lease terms, Onshore Oil and Gas Orders, NTL's; and with other orders and instructions of the authorized officer.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

### DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and <u>NOT</u> by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- Cement baskets shall not be run on surface casing.
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.

Page 5 of 7 Well: GMB W-7-9-17 5/3/2011

• The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.

- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM,
   Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the <u>top of cement</u> and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- Please submit an electronic copy of all other logs run on this well in LAS format to UT\_VN\_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

Page 6 of 7 Well: GMB W-7-9-17 5/3/2011

### **OPERATING REQUIREMENT REMINDERS:**

 All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.

- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at <a href="www.ONRR.gov">www.ONRR.gov</a>.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
  - o Operator name, address, and telephone number.
  - Well name and number.
  - o Well location (1/41/4, Sec., Twn, Rng, and P.M.).
  - Date well was placed in a producing status (date of first production for which royalty will be paid).
  - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
  - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
  - Unit agreement and/or participating area name and number, if applicable.
  - o Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

Page 7 of 7 Well: GMB W-7-9-17 5/3/2011

• All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.

- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover
  equipment shall be removed from a well to be placed in a suspended status without prior approval of
  the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior
  approval of the BLM Vernal Field Office shall be obtained and notification given before resumption
  of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

# S>UC\ BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Ross 29 Submitted By Branden Arnold Phone Number 435-401-0223 Well Name/Number GMB W-7-9-17 Qtr/Qtr NE/NW Section 18 Township 9S Range 17E Lease Serial Number <u>UTU-72106</u> API Number 013-50513 Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string. Date/Time  $\frac{7/8}{11}$  9:00 AM  $\bowtie$  PM  $\bowtie$ <u>Casing</u> – Please report time casing run starts, not cementing times. **Surface Casing Intermediate Casing** Production Casing Liner Other Date/Time  $\frac{7/8}{11}$   $\frac{3:00}{1}$  AM PM **BOPE** Initial BOPE test at surface casing point BOPE test at intermediate casing point 30 day BOPE test Other Date/Time \_\_\_\_\_ AM PM Remarks \_\_\_\_\_

OPERATOR: NEWFIELD PRODUCTION COMPANY

ADDRESS: RT. 3 BOX 3630

**MYTON, UT 84052** 

OPERATOR ACCT. NO. N2695

CODE	ENTITY NO.	ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION SPINO		SPLIO	T FFFFATTI			
		1010			CQ	sc	91	2W	COUNTY	SPUD DATE	EFFECTIVE DATE
A	99999	18125	4301350318	UTE TRIBAL 2-7-4-2	NWNE	7	48	3	DUCHESNE	7/13/2011	7/21/11
WELL 10	COMMENTS:					<u> </u>	† ···	-	POORILOITE	1/13/2011	1/0////
	GRRU						ĺ			T-M-C-M-C	
ACTION	CURRENT	NEW	API NUMBER	WELL NAME							
CODE	ENTITY NO.	ENTITY NO.	/	ASELL LOUNE	QQ	sc	TP	ATION RG	COUNTY	SPUD DATE	EFFECTIVE
В	99999	17400	4301350513	GMBU W-7-9-17	NENW	18	98	17E	DUCHESNE		7/2///
	a and				6		I	-L	- <del></del>	17072011	1401/11
1 (	SCRV			BH=	An a	7	51	) < 6	-	-	
ACTION CODE	CURRENT	NEW L	API NUMBER	· · · · · · · · · · · · · · · · · · ·	<u>wec</u>	<u>'</u>					
COOE	CURRENT ENTITY NO.	NEW ENTITY NO.	ALIMONDEA	WELL NAME	- aa	sc	WELL	LOCATION RG	COUNTY	SPUD DATE	EFFECTIVE
В	99999	17400	4301350472	GMBU T-10-9-16	NWSW	10	98	16E	DUCHESNE	7/8/2011	7/21/11
GRRV BHL = Sec 10 SESE											
ACTION	CURRENT	I New I			<i>RIPC</i>	100	u	SE			
ACTION CODE	ENTITY NO.	NEW ENTITY NO.	APINUMBER	WELL NAME	QQ	sc [	WELL (	OCATION	COUNTY	SPUD DATE	EFFECTIVE
В	99999	17400	4304751546	GMBU B-36-8-17	NWNE	36	88		UINTAH	7/7/2011	7/21/11
G	FRRV			BHL= N				4			-
ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME				OCATION		SPUD	EFFECTIVE
						sc	TP	RG	COUNTY	DATE	DATE
Α	99999	18126	4304751308	UTE TRIBAL 7-3-4-1E	SWNE	3	48	1E	UINTAH	6/28/2011	7/21/11
G	SPRIV										
ACTION	CURRENT	NEW	APINUMBER	WELL NAME			WELL L	OCATION		SPUD	FECTORIN
JULE !	ENTITY NO.	ENTITY NO.			00	sc	TP	RG	COUNTY	DATE	EFFECTIVE DATE
В	99999	17400	4304751550	GMBU J-2-9-17	NENE	2	98	17E	UINTAH	7/15/2011	7/21/11
(	JRRV			BAL = SI	ENE					-	
ACTION CO	DES (See Instructions on back	k of form)									

A - 1 new entity for new well (single well only)

B ~ rwell to existing entity (group or unit well)

C - from one existing entity to another existing entity

D - well from one existing entity to a new entity

E - ther (explain in comments section)

**RECEIVED** 

JUL 2 1 2011

Jentri Park

**Production Clerk** 

07/20/11

FORM 3160-5	
(August 2007)	

(August 2007) D  SUNDRY  Do not use the abandoned we	Of	06			
SUBMIT IN	TRIPLICATE - Other	7. If Unit or CA/A	greement, Name and/or		
1. Type of Well	<b>-</b>			GMBU	
2. Name of Operator	Other			8. Well Name and GRTR MON BU	
NEWFIELD PRODUCTION CO	MPANY			9. API Well No.	11E W-7-9-17
3a. Address Route 3 Box 3630		3b. Phone (include are	e code)	4301350513	
Myton, UT 84052		435,646,3721		10. Field and Pool	, or Exploratory Area
06911	Sec., T., R., M., or Survey Descr. <sup>2</sup> NL 2054 FWL	iption)		GREATER MB	
שיו	NE 4039 FWL	•		11. County or Pari	sn, State
Section 7 T9S R17E				DUCHESNE, U	T
12. CHECK	APPROPRIATE BOX(F	ES) TO INIDICATE NA	ATURE OF NO	OTICE, OR OT	HER DATA
TYPE OF SUBMISSION		TYP	E OF ACTION		
☐ Notice of Intent ☐ Subsequent Report ☐ Final Abandonment	Acidize Alter Casing Casing Repair Change Plans Convert to Injector	Deepen Fracture Treat New Construction Plug & Abandon Plug Back	Reclamati	te ily Abandon	Water Shut-Off Well Integrity Other Spud Notice
of the involved operations. If the op Final Abandonment Notices shall be inspection.)  On 7/8/11 MIRU Ross #2	r recomplete horizontally, give subst performed or provide the Bond No. of ceration results in a multiple complete if filed only after all requirements, income 6. Spud well @10:00 AM. Iment with 160 sks of class	urface locations and measured and on file with BLM/BIA. Required ion or recompletion in a new inter cluding reclamation, have been co Drill 325' of 12 1/4" hole	d true vertical depths subsequent reports s rval, a Form 3160-4; impleted, and the ope	of all pertinent marker half be filed within 30 shall be filed once testi trator has determined to TIH W/ 7 Jt's 8	rs and zones. Attach the days following completion ing has been completed. hat the site is ready for final 5/8" J-55 24# csgn. Set

I hereby certify that the foregoing is true and correct (Printed/ Typed)	Title					
Britt Stubbs	Spud Rig Foreman					
Signature Signature	Date 07/12/2011					
THIS SPACE FOR FEDERAL OR STATE OFFICE USE						
Approved by	Title	Date				
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office					

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

RECEIVED

(Instructions on page 2)

JUL 1 9 2011

# **NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT**

			8 5/8"	_CASING SET AT		326.62	-		
LAST CASING			10	: •		R GMBU W		Exploration	Company
DATUM TO CUT				-			Monumen	nt Butte	
DATUM TO BRA	DENHEAD.	FLANGE	12			_			
TD DRILLER	325	LOGG	€R						
HOLE SIZE	12 1/4"			_					
LOG OF CASING	3 STRING:								
PIECES	OD	ITEM - M	AKE - DES	CRIPTION	WT/FT	GRD	THREAD	CONDT	LENGTH
1		Well Head						Α	1.42
8	<u> </u>	casing (sho	oe jt 46.00)		24	J-55	STC	A	314.3
1		guide shoe	!					Α	0.9
		<u> </u>							
		<u> </u>							
	<u> </u>								
	<u> </u>								
	<u> </u>	<u> </u>							
								<u> </u>	
	<u> </u>	<u> </u>							
	<u> </u>	<u> </u>					<u> </u>		
		Ĺ	T	T					
CASING INVENT			FEET	JTS	1	NGTH OF S		!	316.62
TOTAL LENGTH		<u>3</u>	316.62	7	4	OFF PIEC		ı	2
LESS NON CSG.			2.32		4		CUT OFF CS	G	12
PLUS FULL JTS.		,	0	ļ	CASING SI	ET DEPTH		!	326.62
	TOTAL		314.3	7	Į₁				
TOTAL CSG. DE	L. (W/O TH	RDS)	<b> </b>		]	<b>NRE</b>			
	IMING								
BEGIN RUN CSG	<del>3</del>	Spud	10:00 AM	· · · · · · · · · · · · · · · · · · ·	1		OB		
CSG. IN HOLE			3:00 AM		1		URFACE	·	
BEGIN CIRC			10:07 AM		RECIPROC	CATED PIP	_ No		
BEGIN PUMP CN			10:18 AM		1				
BEGIN DSPL. CN	<b>√</b> T		12:29 PM	7/12/2011	BUMPED F	LUG TO _	320		

10:30 AM

7/12/2011

PLUG DOWN

CEMENT US	ED		CEMENT COMPANY-	BJ Services					
STAGE	# SX		CEMENT TYPE & ADDITIVES						
1	160	Class "G"+2%CaCl Mixed@	15.8ppg W/1.17 yield returned	4 bbls to pit					
	_								
	-								
				And the second s					
		HER PLACEMENT		SHOW MAKE & SPACING					
Middle of firs	t, top of sec	ond and third for a tota	of three.						
COMPANY RE	EPRESENTA	TIVE Britt Stubl	os	DATE <b>7/12/2011</b>					

Sundry Number: 18387 API Well Number: 43013505130000

	STATE OF UTAH		FORM 9
	DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MININ	lG	5.LEASE DESIGNATION AND SERIAL NUMBER: UTU-72106
SUND	N WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
	sals to drill new wells, significantly deepen exingged wells, or to drill horizontal laterals. Use in the contract of the cont		7.UNIT or CA AGREEMENT NAME: GMBU (GRRV)
1. TYPE OF WELL Oil Well			8. WELL NAME and NUMBER: GREATER MON BUTTE W-7-9-17
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COM	IPANY		9. API NUMBER: 43013505130000
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84		NUMBER:	9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0691 FNL 2054 FWL			COUNTY: DUCHESNE
QTR/QTR, SECTION, TOWNSH	IP, RANGE, MERIDIAN: 3 Township: 09.0S Range: 17.0E Meridian: S		STATE: UTAH
11. CHE	CK APPROPRIATE BOXES TO INDICATE I	NATURE OF NOTICE, REPORT,	OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	CHANGE TO PREVIOUS PLANS  CHANGE WELL STATUS  DEEPEN  OPERATOR CHANGE  PRODUCTION START OR RESUME  REPERFORATE CURRENT FORMATION  TUBING REPAIR  WATER SHUTOFF  WILDCAT WELL DETERMINATION  OMPLETED OPERATIONS. Clearly show all pertine completed on 08/17/2011. Attack status report.	hed is a daily completion A U Oil	
NAME (PLEASE PRINT) Jennifer Peatross	PHONE NUMBER 435 646-4885	TITLE Production Technician	
SIGNATURE N/A	450 040-4885	DATE 9/9/2011	
		-, -,	

Summary Rig Activityndry Number: 18387 API Well Number: 43013505130000

# **Daily Activity Report**

Page 1 of 3

Format For Sundry
GMBU W-7-9-17
6/1/2011 To 10/30/2011

8/3/2011 Day: 1 Completion

Rigless on 8/3/2011 - Ran CBL and perforated 1st stage. SIWFN w/ 144 BWTR. - NU Cameron BOP's. RU Hot oiler & test casing, WH head, Casing valves & BOP to 4500 psi. RU WLT w/ mast & pack off tool. Run CBL under pressure. WLTD was 6032' w/ TOC @ 55'. RIH w/ 3 1/8" ported guns & perforate CP2 sds @ 5626- 27', 5616- 19' & CP1 sds @ 5533-37' w/ (11 gram, .36"EH, 16.82; pen. 120°) 3 spf for total of 24 shots. RD WLT & Hot Oiler. SIWFN w/ 144 BWTR.

Daily Cost: \$0

Cumulative Cost: \$15,733

8/8/2011 Day: 2 Completion

Rigless on 8/8/2011 - Frac stg 1, RU The Perforators to perf stg 2. SWIFN. - Crew travel and safety meeting. RU BJ Services. Frac stg 1- CP2/CP1 sds as shown in stimulation report. 652 BWTR. - - - - - RU The Perforators wireline. Set CFTP @ 5340' & perf stg 2- LODC/A3 sds as shown in perforation report. SWIFN.

Daily Cost: \$0

Cumulative Cost: \$20,533

8/10/2011 Day: 3 Completion

Rigless on 8/10/2011 - Frac stg 2-4. Screened out each stg. Had to FB to pit and dump bail HCL each time. - RU The Perforators wireline. Set CFTP @ 4920' & perf stg 4- D1 sds as shown in perforation report. RU BJ Services. Prepare to frac stg 4- D1 sds as shown in stimulation report. No formation breakdown. RU The Perforators to dumpbail 10 gallons HCL. POOH w/WL to find broken glass but dump bailer was plugged w/ 10" of sand. Recovered 7 gallons of HCL. Tried to break down formation again with no luck. RU to dump bail on stg 4 perfs again. Dumped HCL 20' above perfs and POOH. RU BJ Services to frac stg 4- D1 sands as shown in stimulation report. Screened out with 32.2 BWTR left to flush. Open well to pit for immediate flowback @ approx. 3 bpm. Well flowed for 4 hrs & cleaned up. Recovered 720 bbls wtr. 383.5 BWTR. - Safety Meeting, discussed location hazards, recent NFX incidents, job procedure, emergency plans, meeting point. RU BJ Services. Frac stg 2- LODC/A3 sds as shown in stimulation report. Screened out with 34 BW left to flush. Open well to pit for immediate flowback @ approx. 3 bpm. Well flowed for 2.25 hrs & cleaned up. Recovered 405 bbls wtr. 755 BWTR. - RU The Perforators wireline. Set CFTP @ 5120' & perf stg 3- B2 sds as shown in perforation report. RU BJ Services. Prepare to frac stg 3- B2 sds as shown in stimulation report. No formation breakdown. RU The Perforators to dumpbail 10 gallons HCL. RU BJ Services to frac stg 3- B2 sands as shown in stimulation report. Screened out with 76.5 BWTR left to flush. Open well to pit for immediate flowback @ approx. 3 bpm. Well flowed for 2.5 hrs & cleaned up. Recovered 450 bbls wtr. 704.3 BWTR.

Daily Cost: \$0

Cumulative Cost: \$29,156

8/11/2011 Day: 4 Completion

Nabors #1608 on 8/11/2011 - Set CFTP @ 4245' and perf stg 5. Frac stg 5 and RDMO frac

RECEIVED Sep. 09, 2011

Summary Rig Activityndry Number: 18387 API Well Number: 43013505130000

Page 2 of 3

crew and equip. FB well and RIH to set KP @ 3970'. BO well, RDMOWL. MIRUWOR, set pipe racks, unload tbg, and ND/NU BOPS. RIH w/ 4-3/4" mill and 100 jts of 2-7/8" tbg. SWIFN. - Open well to pit for immediate flowback @ approx. 3 bpm. Well flowed for 3 hrs & cleaned up. RU the Perforators to set KP @ 3970'. BO well and RDMOWL. Recovered 540 BW. 438.4 BWTR. MIRUWOR. Spot pipe racks and trailer. Unload tbg and ND frac BOPS. NU 5K Shaffer BOPS, rig floor, and tbg equipment. Prep tbg and tally. PU, MU and RIH w/ 4-3/4" mill, and 100 jts 2-7/8" tbg. RU pump and lines. SWIFN. WOT @ 3240'. - - Safety Meeting, discussed location hazards, recent NFX incidents, job procedure, emergency plans, meeting point. RU BJ Services. RU The Perforators wireline. Set CFTP @ 4245' & perf stg 5- GB6/GB2 sds as shown in perforation report.

Daily Cost: \$0

Cumulative Cost: \$173,963

### 8/12/2011 Day: 5

Completion

Nabors #1608 on 8/12/2011 - DO/CO to 5090'. Circ well cln and SWIFN. - Safety Meeting, discussed location hazards, recent NFX incidents, job procedure, emergency plans, meeting point. SICP @ 0. Prep and tally 2nd row of tbg. RIH w/tbg to tag @ 3960'. LD 1 jt and strip on washington rubber for DO/CO. RU pwr swvl and pump. Catch circ and wash through 10' of sand to plg #1 @ 3970'. Mill out plg in 25 min. RIH on swvl. Tag @ 4132'. Catch circ and wash through 113' of sand to plg #2. Mill out in 20 min. Hang swvl back and RIH to tag @ 4415'. RU pwr swvl and catch circ. Wash through 505' of sand to plg #3 @ 4920'. Mill out in 25 min. RIH on swvl to tag @ 4952'. Catch circ and wash through 168' of sand to plg #4 @ 5120'. Mill out in 25 min. Circ well clean and SWIFN. EOT @ 5090'.

Daily Cost: \$0

Cumulative Cost: \$181,998

### 8/15/2011 Day: 6

Completion

Nabors #1608 on 8/15/2011 - Finish DO/CO to PBTD. Cric cln and swab back remaining sand returns. POOH. - Safety Meeting, discussed location hazards, recent NFX incidents, job procedure, emergency plans, meeting point. SICP 425 PSI - SITP 400 PSI. Pump 60 BW DWN TBG & BO CSG. Swvl into plg #5 to tag @ 5320'. Break Circ & CO 20' sand to plg #5 @ 5340'. DO in 30 min. Hang swvl back and RIH w/tbg to tag @ 5461'. R/U PWR SWVL & Break Circ. CO 605' Sand to PBTD @ 6066'. Circ well cln for 2 hrs. RD PWR SWVL and TOOH w/4 jts 2 7/8" J -55 TBG. EOT @ 5945'. R/U SWAB LUBE & tie new flags onto sand line. Starting Fld Ivl @ Surface. Make 15 swab runs & bring back 170 BW. Ending fld Ivl @ 1400'. R/D Swab lube & SWIFN. EOT @ 5945'.

Daily Cost: \$0

Cumulative Cost: \$187,970

### 8/16/2011 Day: 7

Completion

Nabors #1608 on 8/16/2011 - RIH to CO any new fill. Pump kill and POOH to RBIH w/Prod string. Xover to rod equip and RIH with rods/pump. - Safety Meeting, discussed location hazards, recent NFX incidents, job procedure, emergency plans, meeting point. SICP 550 PSI, SITP 550 PSI. BO csg & pump 60 BW dwn tbg for a kill. RIH w/tbg to tag @ 6066'. No new fill. Circ well w/240 BW to kill. LD 12 JTS 2 7/8" J -55 tbg and TOOH W/177 JTS 2 7/8" J -55 TBG. LD PSN bitsub/bit. PU MU & RIH w/ NC, 2 JTS 2 7/8" J -55 TBG, PSN, 1 jt, TAC, 60 jts jts 2 7/8" J -55 tbg. CSG came on. Shut down and stab washington rubber. Top kill tbg w/20 BW. Cont RIH w/114 JTS 2 7/8" J -55 tbg. CIRC well w/200 BW to kill. Tie back single fast. RD workfloor and equip. ND BOPS and PU MU tbg hanger. Land well on hanger w/18000# tension. NU B -1 adptr & prodtee. Change over to rod equip. Tie back double fast. PU & prime

Summary Rig Activity ndry Number: 18387 API Well Number: 43013505130000 Page 3 of 3

new pump. RIH w/rods as detailed. PU polish rod SWIFN. EOP @ 4600'.

Daily Cost: \$0

Cumulative Cost: \$193,605

8/17/2011 Day: 8

Completion

Nabors #1608 on 8/17/2011 - Finish running rods. Seat pump and test to 800 psi. Hang head and PWOP. - Safety Meeting, discussed location hazards, recent NFX incidents, job procedure, emergency plans, meeting point. Change oil in rig. SICP @ 300 psi, SITP @ 200 psi. BO csg, pump 40 BW for a tbg kill. LD polish rod and con't RIH w/rods as detailed. PU polish rod and seat pump. Fill tbg with 8 BW. RU unit and stroke test to 800 psi w/unit. RDMOWOR.

Finalized
Daily Cost: \$0

Cumulative Cost: \$272,092

Pertinent Files: Go to File List

Form 3160-4 (August 2007)

# **UNITED STATES** DEPARTMENT OF THE INTERIOR

FORM APPROVED OMB NO. 1004-0137

				BURE	EAU OF	LAND MA	NA	GEME	NT		·						Expires: Ju		
	v	/ELL (	СОМР	LETIC	ON OR F	RECOMPLI	ETI	ON REF	PORT	AND L	_og				5. L	ease Se	erial No.		
															UTL	J-721	06		
la. Type of	Well		Dil Well		Gas Well			Other	<u> </u>							Indiar	, Allottee or	Tribe	Name
b. Type of	Completion			, LJ,	Work Over	Deepen [	P	lug Back	☐ Dif	f, Resvr.	,				<b>NA</b> 7. U	nit or (	CA Agreeme	nt Na	me and No.
			Other:												GRE	EATE	R MONUM	ENT	BUTTE
<ol><li>Name of NEWFIEL</li></ol>	Operator DEXPLO	RATIO	N COM	PANY											GM	BU W	ame and Wel -7-9-17	II No.	
3. Address	1401 17TH	ST. SUIT	E 1000 D	ENVER.	CO 80202				Phone 1		ude ar	rea code	<i>(</i> )			FI We 013-50			
4. Location						lance with Fede	eral r								10. 1	Field a	nd Pool or E		atory
At curfa	CE 0041 EL		C 41 E141			. 18, T9S, R1	7F /	(UTU 704	06)						11 9	Sec T	., R., M., on	Block	and
At Surray	~ 691 FN	1L & 2U	154° FVV	L (NE/I	AVV) SEC.	. 18, 195, KT	/= (	010-721	00)						S	Survey	or Area	C. 18. T	198. R17E
At top pr	od. interval	reported	l below	16' FSL	<b>.</b> & 2574'	FWL (SE/SW	/) SE	EC. 7. T9	S. R17E	E (UTU-	7210	(6)					or Parish		13. State
			241	. (									_		DUC	HES	NE		UT
At total d	epth 100	rol a	115	Date T	D. Reache	C. 7, T9S, R1	7 = 1	16 D	ate Com	3HL			Ω				ons (DF, RK		
07/08/201	11		0	7/25/20	11				D&A	<b>✓</b> F	Ready	to Prod.			5440	)' GL	5452' KB	,	
18. Total D		D 611			19. Ph	ig Back T.D.:	MI TV	06066' D 59	53		20. D	epth B	idge	Plug S		MD TVD			
21. Type E	lectric & Ot	her Mecl	nanical L									Was wel			Z N		Yes (Subm Yes (Subm		
						EUTRON,GR	,CA	LIPER, C	МТ ВО	ND	j	Was DS' Direction	run nal St	arvey?	N	• <b>7</b>	Yes (Subm	it cop	y)
23. Casing	T							Stage Ce	menter	No.	of Sk	s. &	s	lurry V	ol.			T	
Hole Size	Size/G1		Wt. (#/ft.	4	op (MD)	Bottom (M	D)	Dep		Туре	of Ce	ment		(BBL)		Cei	ment Top*	-	Amount Pulled
12-1/4"	8-5/8" J		24#	0		325' 6090'				160 C 260 P						55'		-	
7-7/8"	5-1/2" J	-55	15.5#	- 10		0090				426 50									
				-						1200		<u> </u>							
				1															
									-									L,	
24. Tubing		Set (ME	)) Pac	ker Dep	th (MD) T	Size		Depth Set	(MD)	Packer	Depth	(MD)		Size	Т	Dep	oth Set (MD)	1	Packer Depth (MD)
2-7/8"	EOT@	5698		5598	· · · · · ·														
25. Produci	ing Intervals Formatio			т	op do	Bottom			foration lorated In			Т 9	ize		No. I	Ioles		Pe	rf. Status
A) Green				5135'	<del>op</del>	5627'		5135-562		torrur		.36"		1	54				1
B)																			
C)																-2	+	\	nu .
D)		·	<u> </u>	1												-		wa i V	Burn har
27. Acid, F	Depth Inter		Cement	squeeze	, etc.					Amount	and Ty	ype of N	later	ial			DEC 0	1	2011
5135-5627	7'		ı	rac w/	240443#	s 20/40 white	sar	nd in 158	6 bbls o	f Lightr	ning 1	7 fluid	in 2	stage	s.		DEC **	•	
										_			-			DIV	<del>: 07 014, (</del>	CAS.	<u> 2 MINING</u>
		_	-+		–														
28. Product	ion - Interv	al A																	
Date First Produced	Test Date	Hours Tested	Test		Oil BBL	Gas MCF	Wa BB		Oil Grav Corr. Al		Ga Gr	as ravity		Produc			20' v 21' v	24' 5	RHAC Pump
8/15/11	8/25/11		1100	uction	36	6	9		Con. A	. 1	, Pi	avity		2-1/2	X 1~	) <del> </del>	20 X 21 X	Z4 I	and rump
Choke	Tbg. Press.	24 Csg.	24 H	r.	Oil	Gas	Wa	ter	Gas/Oil		W	ell Stati	ıs	<u> </u>	······································				
Size	Flwg.	Press.	Rate		BBL	MCF	BB		Ratio			RODU		G					
	SI		-	<b>▶</b>															
28a. Produc			hr.		lo:t		haz	ton	Dil C	,it.,	Ga	20		Produc	tion M	ethod			
Date First Produced	Test Date	Hours Tested	Test Prod		Oil BBL	Gas MCF	Wa BB		Oil Grav Corr. Al		- 1	as ravity		r rouuc	ALIOH IVI	viii0U			
			-	▶															
Choke	Tbg. Press.		24 H		Oil	Gas	Wat		Gas/Oil		W	ell Statu	ıs						, , , , , , , , , , , , , , , , , , , ,
Size	Flwg. SI	Press.	Rate		BBL	MCF	BB	ட	Ratio										

<sup>\*(</sup>See instructions and spaces for additional data on page 2)

20h Prod	uction - Inte	rvol C										
Date First		Hours	Test	Oil	Gas	Water	Oil Gravi			Production Method		
Produced		Tested	Production	BBL	MCF	BBL	Corr. API	I G	ravity			
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	w	ell Status			
20a Duod	uation Into	mol D										
	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravi Corr. API		as ravity	Production Method		
Choke Size	Tbg. Press. Flwg. S1	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	w	ell Status			
29. Dispo	sition of Gas	Solid, us	sed for fuel, ve	ented, etc.,	<del>)</del>		Y					-
USED FOR	RFUEL											
30. Sumn	nary of Poro	us Zones	(Include Aqui	ifers):				3	1. Formati	on (Log) Markers		
Show a includi recover	ng depth int	zones of perval teste	porosity and c	ontents thed, time to	ereof: Cored ol open, flow	intervals and al ing and shut-in	ll drill-stem ter pressures and	sts,	SEOLOGI	ICAL MARKERS		VIII.
		Т	D-44		Dan	criptions, Conte	onto oto			Name	Тор	
FOIT	nation	Тор	Bottom		Des	criptions, cont	enis, etc.			1 tantie	Meas. Deptl	h
GREEN RIV	/ER	5135'	5627'						ARDEN GU ARDEN GU		3615' 3822'	
									GARDEN GU POINT 3	LCH 2	3934' 4194'	
									( MRKR ( MRKR		4464' 4499'	
									OUGLAS CI II CARBONA		4630' 4873'	
			·						LIMESTON CASTLE PEA		4996' 5488'	
									ASAL CARB /ASATCH	SONATE	5939' 6070'	
					,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,							
32. Additi	ional remark	s (include	plugging pro	cedure):								
										1		
33. Indica	te which iter	ms have b	een attached b	y placing	a check in the	e appropriate bo	oxes:					
Elec	trical/Mecha	nical Logs	(1 full set req'	d.)		Geologic Repor	ort 🔲	DST Report		✓ Directional Survey		
Sun	dry Notice fo	r plugging	and cement ve	rification		Core Analysis	Z	Other: Drilli	ng Daily A	Activity		_
					rmation is cor	nplete and corre				ecords (see attached instructions)*		
N	ame (please	prifit) Je	nnifer Peatr	oss				duction Te	chnician		<del></del>	
Si	gnature	TU	ICT Y UP	1		<u></u>	Date 10/0	05/2011				
Title 18 U.	S.C. Section	1001 and	l Title 43 U.S. ements or rep	C. Section	n 1212, make ns as to any m	it a crime for an	ny person kno jurisdiction.	wingly and v	willfully to	make to any department or agency	of the United States	any
(Continue)											(Form 3160-4	nage 2)

ķ

.



# **NEWFIELD EXPLORATION**

USGS Myton SW (UT) SECTION 18 T9S R17E W-7-9-17

Wellbore #1

Design: Actual

# **Standard Survey Report**

27 July, 2011





Survey Report



NEWFIELD EXPLORATION Company: Project: USGS Myton SW (UT) Site: SECTION 18 T9S R17E

Well W-7-9-17 Wellbore: Wellbore #1 Design: Actual

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Database:

Survey Calculation Method:

Well W-7-9-17

W-7-9-17 @ 5452.0ft (Newfield Rig #3) W-7-9-17 @ 5452.0ft (Newfield Rig #3)

Minimum Curvature

EDM 2003,21 Single User Db

Project USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA

Map System: Geo Datum:

US State Plane 1983

North American Datum 1983 Utah Central Zone

System Datum:

Mean Sea Level

Map Zone:

SECTION 18 T9S R17E Site

Site Position: From: Position Uncertainty:

Map

Northing: Easting: Slot Radius: 7,183,900.00 ft 2,049,800.00ft Latitude: Longitude:

40° 1' 56.921 N 110° 2' 16.332 W

**Grid Convergence:** 0.94°

Well W-7-9-17, SHL LAT: 40° 02' 10.38, LONG: -110° 03' 03.63

0.0 ft

Well Position

+N/-S +E/-W

0.0 ft 0.0 ft Northing: Easting:

7,185,201.75 ft 2,046,099.69 ft Latitude: Longitude:

40° 2' 10.380 N 110° 3' 3.630 W

Position Uncertainty

0.0 ft

Wellhead Elevation:

5,452.0 ft

**Ground Level:** 

5,440.0 ft

Wellbore Wellbore #1 Magnetics Declination Dip Angle Field Strength Model Name Sample Date (nT) (°) (°) 52,342 IGRF2010 2010/09/15 65.81 11 40

Actual Design Audit Notes: ACTUAL 0.0 Version: 1.0 Phase: Tie On Depth: Direction Vertical Section: Depth From (TVD) +N/-S +E/-W (ft) (ft) (ft) (°) 0.0 0.0 0.0 36.47

Date 2011/07/27 Survey Program From To Survey (Wellbore) (ft) (ft) Description **Tool Name** MWD - Standard 6,112.0 Survey #1 (Wellbore #1) MWD 296.0

Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth (ft)	Inclination (°)	Azimuth (°)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Section (ft)	Rate (°/100ft)	Rate (°/100ft)	Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
296.0	0.83	282.63	296.0	0.5	-2.1	-0.9	0.28	0.28	0.00
326.0	0.93	339.52	326.0	0.7	-2.4	-0.8	2.81	0.33	189.63
358.0	1.14	335.06	358.0	1.3	-2.6	-0.5	0.70	0.66	-13.94
388.0	0.86	351.45	388.0	1.8	-2.8	-0.2	1.33	-0.93	54.63
419.0	1.01	342.62	419.0	2.3	-2.9	0.1	0.67	0.48	-28.48
449.0	0.79	351.01	449.0	2.7	-3.0	0.4	0.85	-0.73	27.97
480.0	0.33	2.20	480.0	3.0	-3.0	0.6	1.52	-1.48	36.10
510.0	0.26	0.26	510.0	3.2	-3.0	8.0	0.24	-0.23	-6.47
541.0	0.18	80.53	541.0	3.2	-3.0	8.0	0.94	-0.26	258.94
571.0	0.31	25.95	571.0	3.3	-2.9	1.0	0.84	0.43	-181.93
602.0	0.53	37,24	602.0	3.5	-2.8	1.2	0.75	0.71	36.42
633.0	0.70	36.32	633.0	3.8	-2.6	1.5	0.55	0.55	-2.97



Survey Report



Company: Project:

Site:

NEWFIELD EXPLORATION USGS Myton SW (UT) SECTION 18 T9S R17E

Well: W-7-9-17
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference:

TVD Reference: MD Reference:

Database:

North Reference: Survey Calculation Method: Well W-7-9-17

W-7-9-17 @ 5452.0ft (Newfield Rig #3) W-7-9-17 @ 5452.0ft (Newfield Rig #3)

True

Minimum Curvature

y Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth (ft)	Inclination (°)	Azimuth (°)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Section (ft)	Rate (°/100ft)	Rate (°/100ft)	Rate (°/100ft)
663.0	1.14	35.31	663.0	4.2	-2.3	2.0	1.47	1.47	-3.37
694.0	1.49	39.57	694.0	4.7	-1.9	2.7	1.17	1.13	13.74
724.0	2.01	44.75	723.9	5.4	-1.2	3.6	1.81	1.73	17.27
755.0	2.07	41.11	754.9	6.2	-0.5	4.7	0.46	0.19	-11.74
785.0	2.37	42.16	784.9	7.1	0.3	5.9	1.01	1.00	3.50
815.0	2.94	40.49	814.9	8.1	1.2	7.3	1.92	1.90	-5.57
845.0	3.43	37.86	844.8	9.4	2.2	8.9	1.70	1.63	-8.77
877.0	4.17	34.73	876.7	11.1	3.5	11.0	2.40	2.31	-9.78
908.0	4.66	40.10	907.7	13.0	5.0	13.4	2.07	1.58	17.32
939.0	5.14	39.16	938.5	15.1	6.6	16.1	1.57	1.55	-3.03
969.0	5.71	40.18	968.4	17.3	8.5	18.9	1.93	1.90	3.40
1,002.0	6.15	41.68	1,001.2	19.8	10.7	22.3	1.41	1.33	4.55
1,032.0	6.42	43.52	1,031.0	22.2	12.9	25.6	1.12	0.90	6.13
1,064.0	6.90	43.66	1,062.8	24.9	15.5	29.2	1.50	1.50	0.44
1,096.0	7.38	46.47	1,094.6	27.7	18.3	33.2	1.85	1.50	8.78
1,128.0	7.65	49.63	1,126.3	30.5	21.4	37.3	1.54	0.84	9.88
1,159.0	8.23	48.62	1,157.0	33.3	24.6	41.5	1.92	1.87	-3.26
1,190.0	8.75	46.38	1,187.7	36.4	28.0	45.9	1.99	1.68	-7.23
1,222.0	9.27	45.68	1,219.3	39.9	31.6	50.9	1.66	1.63	-2.19
1,253.0	9.80	45.41	1,249.9	43.5	35.3	56.0	1.72	1.71	-0.87
1,285.0	10.20	43.17	1,281.4	47.5	39.2	61.5	1.74	1.25	-7.00
1,317.0	10,68	42.16	1,312.8	51.7	43.1	67.2	1.61	1.50	-3.16
1,348.0	11.51	38.65	1,343.3	56.3	46.9	73.2	3.45	2.68	-11.32
1,380.0	11.73	37.39	1,374.6	61.4	50.9	79.6	1.05	0.69	-3.94
1,411.0	12.22	35.70	1,404.9	66.5	54.7	86.0	1.94	1.58	-5.45
1,443.0	12.79	35.31	1,436.2	72.2	58.8	93.0	1.80	1.78 1.06	-1.22 -2.55
1,474.0	13.12	34.52	1,466.4	77.9	62.7	99.9	1.21		
1,506.0	13.27	34.12	1,497.5	83.9	66.9	107.2	0.55	0.47	-1.25
1,537.0	13.23	33.55	1,527.7	89.8	70.8	114.3	0.44	-0.13	-1.84
1,569.0	13.05	32.05	1,558.9	95.9	74.8	121.6	1.20 0.81	-0,56 -0,42	-4.69 3.06
1,600.0 1,632.0	12.92 12.70	33.00 33.50	1,589.1 1,620.3	101.8 107.7	78.5 82.4	128.5 135.6	0.81	-0.69	1.56
1,663.0	12.04 11.95	35.61 35.97	1,650.6	113.2	86.2 90.0	142.2 148.9	2.58 0.37	-2.13 -0.28	6.81 1.13
1,695.0 1,727.0	11.95	35.97 34.73	1,681.9 1,713.2	118.6 123.9	90.0	155.5	1.14	-0.26 -0.81	-3.88
1,758.0	11.78	32.49	1,743.5	129.2	97.3	161.7	1.50	0.29	-7.23
1,789.0	12.17	31.92	1,773.9	134.6	100.8	168.2	1.31	1.26	-1.84
		32.10			104.4	175.0	1.38	1.38	0.56
1,821.0 1,853.0	12.61 12.35	32.10	1,805.1 1,836.4	140.5 146.3	104.4	175.0	0.97	-0.81	-2.47
1,884.0	12.39	32.23	1,866.6	152.0	111.5	188.5	0.65	0.13	2.97
1,916.0	12.06	33.85	1,897.9	157.7	115.2	195.3	1.49	-1.03	5.06
1,947.0	11.91	34.12	1,928.2	163.0	118.8	201.7	0.52	-0.48	0.87
1,979.0	12.00	33.90	1,959.5	168,5	122.5	208.3	0.32	0,28	-0.69
2,011.0	12.26	34.78	1,999.8	174.1	122.3	215.1	1.00	0.28	2.75
2,042.0	12.35	34.52	2,021.1	179.5	130.1	221.7	0.34	0.29	-0.84
2,074.0	12.17	34.30	2,052.4	185.1	133.9	228.4	0.58	-0.56	-0.69
2,105.0	12.66	33.64	2,082.7	190.6	137.6	235.1	1.65	1.58	-2.13
2,137.0	12.84	34.34	2,113.9	196.5	141.6	242.2	0.74	0.56	2.19
2,169.0	12.74	32.63	2,115.9	202.4	145.5	249.2	1.22	-0.31	-5.34
2,200.0	12.83	34.25	2,175.3	208.1	149.3	256.1	1.19	0.29	5.23
2,232.0	12.35	36.93	2,206.5	213.8	153.3	263.1	2.36	-1.50	8.38
2,263.0	12.08	36.01	2,236.8	219.1	157.2	269.6	1.07	-0.87	-2.97
2,295.0	12.30	35.31	2,268.1	224.5	161.2	276.4	0.83	0.69	-2.19
2,326.0	12.61	34.95	2,298.4	230.0	165.0	283.1	1.03	1.00	-1.16



Survey Report



Company: Project: NEWFIELD EXPLORATION USGS Myton SW (UT)

Site: Well: SECTION 18 T9S R17E W-7-9-17 Wellbore #1

Wellbore: Design:

Actual

Local Co-ordinate Reference:

TVD Reference: MD Reference:

North Reference: Survey Calculation Method:

Database:

Well W-7-9-17

W-7-9-17 @ 5452.0ft (Newfield Rig #3) W-7-9-17 @ 5452.0ft (Newfield Rig #3)

True

Minimum Curvature

							40.0	A STATE OF THE STA	-
Measured Depth	Inclination	Azimuth	Vertical Depth	+N/-S	+E/-W	Vertical Section	Dogleg Rate	Build Rate	Turn Rate
(ft)	mcimauon (°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)
2,358.0	12.61	36.40	2,329.6	235.7	169.1	290.0	0.99	0.00	4.53
2,389.0	12.74	36.19	2,359.9	241.2	173.1	296.8	0.44	0.42	-0.68
	12.74	35.83	2,391.1	246.8	173.1	303.9	0.59	-0.53	-1.13
2,421.0									
2,453.0	12.26	34.12	2,422.3	252.5	181.2	310.7	1.50	-0.97	-5.34
2,484.0	12.13	34.78	2,452.6	257.9	184.9	317.3	0.61	-0.42	2.13
2,515.0	12.30	36.37	2,482.9	263.2	188.7	323.8	1.22	0.55	5.13
2,547.0	12.26	36,49	2,514.2	268.7	192.7	330.6	0.15	-0.13	0.38
2,579.0	12.35	38.12	2,545.5	274.1	196.9	337.5	1.12	0.28	5.09
2,610.0	12.84	39.04	2,575.7	279.4	201.1	344.2	1.71	1.58	2.97
2,642.0	13.71	39.17	2,606.9	285,1	205.7	351.6	2.72	2.72	0.41
2,673.0	14.24	40.36	2,636.9	290.8	210.5	359.0	1.94	1.71	3.84
2,705.0	14.55	40.54	2,667.9	296.9	215.7	367.0	0.98	0.97	0.56
2,736.0	14.77	38.69	2,697.9	302.9	220.7	374.8	1.67	0.71	-5.97
2,768.0	14.94	36.17	2,728.9	309.5	225.7	383.0	2.09	0.53	-7.88
						390.8	2.09	-2.26	-0.81
2,799.0	14.24	35.92	2,758.9	315.8	230.3				
2,831.0	13.45	35.00	2,789.9	322.0	234.7	398.5	2.56	-2.47	-2.88
2,862.0	12.83	32.80	2,820.1	327.9	238.6	405.5	2.57	-2.00	-7.10 2.16
2,894.0	12.57	33.81	2,851.3	333.7	242.5	412.5	1.07	-0.81	3.16
2,926.0	12.48	32.77	2,882.6	339.5	246.3	419.5	0.76	-0.28	-3.25
2,957.0	12.26	31.79	2,912.9	345.2	249.9	426.1	0.98	-0.71	<b>-</b> 3.16
2,989.0	11.38	31.57	2,944.2	350.7	253.3	432.6	2.75	-2.75	-0.69
3,020.0	10.63	31.97	2,974.6	355.8	256.4	438.5	2.43	-2.42	1.29
3,052.0	10.72	30.74	3,006.1	360.8	259.5	444.4	0.77	0.28	-3.84
3,083.0	10.59	32.76	3,036.5	365.7	262.5	450.1	1.28	-0.42	6.52
3,115.0	10.94	35.57	3,068.0	370.6	265.9	456.1	1.97	1.09	8.78
3,146.0	11.34	35.66	3,098.4	375.5	269.4	462.1	1.29	1.29	0.29
3,178.0	11.74	35.66	3,129.7	380.7	273.1	468.5	1.25	1.25	0.00
3,209.0	11.75	36.67	3,160.1	385.8	276.8	474.8	0.66	0.03	3.26
		37.00	3,191.4	391.1	280.8	481.4	1.48	1.47	1.03
3,241.0	12.22					488.3	1.55	1.50	-1.72
3,273.0	12.70	36.45	3,222.6	396.7	284.9				
3,304.0	12.88	37.02	3,252.9	402.2	289.0	495.2	0.71	0.58	1.84
3,336.0	12.92	37.15	3,284.1	407.9	293.3	502.3	0.15	0.13	0.41 2.42
3,367.0	12.70	37.90	3,314.3	413.3	297.5	509.2	0.89	-0.71	
3,399.0	12.30	37.94	3,345.5	418.8	301.8	516.1	1.25	-1.25 0.45	0.13
3,430.0	12.44	36.10	3,375.8	424.1	305.8	522.8	1.35	0.45	-5.94
3,462.0	12.44	36.67	3,407.1	429.6	309.9	529.7	0.38	0.00	1.78
3,493.0	12.17	36.98	3,437.3	434.9	313.8	536.3	0.90	-0.87	1.00
3,524.0	11.87	36.80	3,467.7	440.1	317.7	542.7	0.98	-0.97	-0.58
3,556.0	11.34	35.48	3,499.0	445.3	321.5	549.2	1.85	-1.66	-4.13
3,587.0	11.60	36.01	3,529.4	450.3	325.1	555.3	0.90	0.84	1.71
3,618.0	11.60	35.22	3,559.8	455.3	328.7	561.6	0.51	0.00	-2.55
3,650.0	11.47	34.16	3,591.1	460.6	332.4	568.0	0.78	-0.41	-3.31
3,682.0	11.51	34.51	3,622.5	465.9	336.0	574.3	0.25	0.13	1.09
3,713.0	11.87	35.26	3,652.8	471.0	339.6	580.6	1.26	1.16	2.42
3,744.0	11.95	36.45	3,683.2	476.2	343.3	587.0	0.83	0.26	3.84
		37.37	3,714.5	481.5	347.3	593.6	0.91	-0.69	2.88
3,776.0	11.73								2.87
3,807.0 3,839.0	11.9 <b>4</b> 12.61	38.26 39.83	3,744.8 3,776.1	486.5 491.8	351.1 355.4	599.9 606.7	0.90 2.34	0.68 2.09	2.0 <i>1</i> 4.91
3,870.0	12.83	40.93	3,806.3	497.0	359.9	613.5	1.06	0.71 0.13	3.55 -4.66
3,902.0	12.87	39.44	3,837.5	502.4	364.4	620.6	1.04		
3,933.0	12.39	40.80	3,867.8	507.6	368.8	627.4	1.82	-1.55	4.39
3,965.0	12.17	39.92	3,899.0	512.8	373.2	634.2	0.90	-0.69	-2.75
3,996.0	11.91	41.15	3,929.4	517.7	377.4	640.6	1.18	-0.84	3.97
4,028.0	12.30	39.04	3,960.6	522.8	381.7	647.3	1.84	1.22	-6.59



Survey Report



Company: Project:

NEWFIELD EXPLORATION
USGS Myton SW (UT)

SECTION 18 T9S R17E

Site: Well: Wellbore:

Design:

2011/07/27 10:16:42AM

W-7-9-17 Wellbore #1

Actual

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Database:

Well W-7-9-17

W-7-9-17 @ 5452.0ft (Newfield Rig #3) W-7-9-17 @ 5452.0ft (Newfield Rig #3)

True

Minimum Curvature

Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth (ft)	Inclination (°)	Azimuth (°)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Section (ft)	Rate (°/100ft)	Rate (°/100ft)	Rate (°/100ft)
	- Averegness settlette st. 1	United States			385.9	654.0	1.26	0.87	-4.26
4,059.0	12.57	37.72	3,990.9	528.0 523.6	390.2	661.0	0.83	0.53	2.91
4,091.0	12.74	38.65	4,022.1	533.6	394.4	667.8	1.03	-0.55	-3.97
4,122.0	12.57	37.42	4,052.4	538.9	398.6	674.8	0.78	0.28	-3.31
4,154.0	12.66	36.36	4,083.6	544.5					
4,185.0	12.61	36.10	4,113.9	550.0	402.6	681.6	0.24	-0.16	-0.84
4,217.0	12.08	35.66	4,145.1	555.5	406.6	688.4	1.68	-1.66	-1.38
4,248.0	11.91	34.91	4,175.4	560.8	410.3	694.9	0.74	-0.55	-2.42
4,280.0	11.92	35.24	4,206.8	566.2	414.1	701.5	0.22	0.03	1.03
4,311.0	11.43	32.93	4,237.1	571.4	417.7	707.7	2.18	-1.58	-7.45
4,343.0	11,21	32.93	4,268.5	576.6	421.1	714.0	0.69	-0.69	0.00
4,374.0	11.29	33.50	4,298.9	581.7	424.4	720.0	0.44	0.26	1.84
4,406.0	11.43	36.98	4,330.3	586.8	428.0	726.3	2.19	0.44	10.88
4,438.0	11.43	38.60	4,361.6	591.8	431.9	732.7	1.00	0.00	5.06
4,469.0	11.80	38.18	4,392.0	596.7	435.8	738.9	1.22	1.19	-1.35
								0.23	5.32
4,500.0	11.87	39.83	4,422.3	601.7	439.8	745.3	1.11	0.23	-3.28
4,532.0	12.17	38.78	4,453.6	606.8	444.0	751.9	1.16 1.11	1.09	-3.26 0.97
4,564.0	12.52	39.09	4,484.9	612.2	448.3 452.6	758.8 765.5	0.58	0.58	0.97
4,595.0	12.70	39.18	4,515.2	617.4 622.9	452.6 456.9	765.5 772.5	1.21	-0.81	-4.13
4,627.0	12.44	37.86	4,546.4	022.9	450.9	112.5			
4,659.0	12.00	36.32	4,577.7	628.3	461.0	779.2	1.71	-1.38	-4.81
4,690.0	11.43	35.75	4,608.0	633.3	464.7	785.5	1.88	-1.84	-1.84
4,721.0	11.34	34.16	4,638.4	638.4	468.2	791.7	1.05	-0.29	-5.13
4,753.0	11.21	33.55	4,669.8	643.6	471.7	797.9	0.55	-0.41	-1.91
4,784.0	11.38	34.52	4,700.2	648.6	475.1	804.0	0.82	0.55	3.13
4,816.0	11.87	34.78	4,731.5	653.9	478.8	810.4	1.54	1.53	0.81
4,847.0	11.95	36.76	4,761.9	659.1	482.5	816.8	1.34	0.26	6.39
4,879.0	11.70	38.38	4,793.2	664.3	486.5	823.4	1.30	-0.78	5.06
4,910.0	11.87	38.78	4,823.5	669.2	490.4	829.7	0.61	0.55	1.29
4,938.1	12.02	39.36	4,851.0	673.7	494.1	835.5	0.68	0.53	2.07
W-7-9-17 TG	a medical								
4,942.0	12.04	39.44	4,854.8	674.4	494.6	836.3	0.68	0.53	2.04
4,942.0	12.83	39.83	4,885.1	679.5	498.9	843.0	2.56	2.55	1.26
5,005.0	12.83	39.74	4,916.3	685.0	503.5	850.1	0.41	0.41	-0.28
5,005.0	13.14	37.14	4,946.5	690.5	507.8	857.1	1.98	0.58	-8.39
5,068.0	12.74	37.15	4,977.7	696.2	512.1	864.3	1.25	-1.25	0.03
5,100.0	12.30	36.10	5,008.9	701.8	516.3	871.2	1.55	-1.38	-3.28 0.55
5,131.0	12.39	36.27	5,039.2	707.1	•	877.8	0.31 2.10	0.29 1.66	5.91
5,163.0	12.92	38.16	5,070.4	712.7	524.4	884.8 891.8	0.65	0.13	2.84
5,194.0	12.96	39.04	5,100.6 5.131.8	718.1 723.7	528.8 533.2	898.9	0.53	-0.13	0.16
5,226.0	12.79	39.09	5,131.8						
5,257.0	12.61	38.03	5,162.1	729.0	537.5	905.7	0.95	-0.58	-3.42
5,289.0	12.83	37.68	5,193.3	734.5	541.8	912.8	0.73	0.69	-1.09
5,320.0	12.79	40.05	5,223.5	739.9	546.1	919.6	1.70	-0.13	7.65
5,352.0	12.96	41.28	5,254.7	745.3	550.8	926.7	1.01	0.53	3.84
5,384.0	12.66	40.93	5,285.9	750.6	555.4	933.8	0.97	-0.94	-1.09
5,415.0	12.70	41.06	5,316.2	755.8	559.9	940.6	0.16	0.13	0.42
5,447.0	12.39	39.44	5,347.4	761.1	564.4	947.5	1.47	-0.97	-5.06
5,479.0	11.83	39.31	5,378.7	766.3	568.7	954.2	1.75	-1.75	-0.41
5,510.0	12.00	36.80	5,409.0	771.3	572.6	960.6	1.76	0.55	-8.10
5,541.0	12.30	35.52	5,439.3	776.6	576.4	967.1	1.30	0.97	-4.13
							2.22	2.22	0.03
5,573.0	13.01	35.53	5,470.6	782.3	580.5	974.2 981.2	0.98	0.71	-3.00
5,604.0	13.23	34.60	5,500.7	788.1	584.6	981.2 988.7	2.22	2.19	-1,50
5,636.0 5,667.0	13.93 14.06	34.12 33.39	5,531.9 5,561.9	794.3 800 <i>.</i> 5	588.8 593.0	996.2	0.71	0.42	-2.35



Survey Report



Company: Project: NEWFIELD EXPLORATION USGS Myton SW (UT) SECTION 18 T9S R17E

Well: Wellbore: Design:

Site:

W-7-9-17 Wellbore #1 Actual Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method: Database: Well W-7-9-17

W-7-9-17 @ 5452.0ft (Newfield Rig #3) W-7-9-17 @ 5452.0ft (Newfield Rig #3)

True

Minimum Curvature

Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth (ft)	Inclination (°)	Azimuth (°)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Section (ft)	Rate (°/100ft)	Rate (°/100ft)	Rate (°/100ft)
5,699.0	13.45	34.30	5,593.0	806.8	597.2	1,003.8	2.02	-1.91	2.84
5,730.0	13.23	33.59	5,623.2	812.7	601.2	1,010.9	0.88	-0.71	-2.29
5,762.0	12.79	34.21	5,654.4	818.7	605.2	1,018.1	1.44	-1.38	1.94
5,793.0	12.92	34.87	5,684.6	824.4	609.1	1,025.0	0.63	0.42	2.13
5,825.0	13.01	35.79	5,715.8	830.3	613.3	1,032.2	0.70	0.28	2.88
5,856.0	13.23	35.75	5,746.0	836.0	617.4	1,039.2	0.71	0.71	-0.13
5,888.0	12.74	37.37	5,777.1	841.7	621.7	1,046.4	1.91	-1.53	5.06
5,920.0	12.22	35.92	5,808.4	847.3	625.8	1,053.3	1.90	-1.63	-4.53
5,951.0	11.56	35.70	5,838.7	852.5	629.5	1,059.7	2.13	-2.13	-0.71
5,983.0	11.51	33.44	5,870.1	857.7	633.2	1,066.1	1.42	-0.16	-7.06
6,014.0	11.65	33.85	5,900.4	862.9	636.6	1,072.3	0.52	0.45	1.32
6,045.0	11.21	32.27	5,930.8	868.1	640.0	1,078.5	1.74	-1.42	-5.10
6,060.0	11.14	33.19	5,945.5	870.5	641.5	1,081.4	1.28	-0.47	6.13
6,112.0	10.90	36.38	5,996.6		→ 647.2	1,091.3	1.26	-0.46	6.13

Wellbore Targets					7:14:18(45:14/)				
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting		
- Shape	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(ft)	Latitude	Longitude
W-7-9-17 TGT	0.00	0.93	4,850.0	675.7	499.5	7,185,885.48	2,046,588.15	40° 2' 17.058 N	110° 2' 57.208 V
<ul> <li>actual wellpath mi</li> </ul>		ter by 5.8ft a	at 4938.1ft M	ID (4851.1 TVD	, 673.8 N, 49	94.1 E)			
- Circle (radius 75.0	)								

Checked By:	Approved By:	Date:
l		



Project: USGS Myton SW (UT) Site: SECTION 18 T9S R17E


Well: W-7-9-17 Wellbore: Wellbore #1


SURVEY: Actual



Azimuths to True North Magnetic North: 11.40°

Magnetic Field Strength: 52341.7snT Dip Angle: 65.81° Date: 2010/09/15 Model: IGRF2010





FINAL SURVEY REPORT



Design: Actual (W-7-9-17/Wellbore #1)

Created By: Sarah Webb Date: 10:18, July 27 2011 THIS SURVEY IS CORRECT TO THE BEST OF MY KNOWLEDGE AND IS SUPPORTED BY ACTUAL FIELD DATA.

# **Daily Activity Report**

# Format For Sundry GMBU W-7-9-17 5/1/2011 To 9/30/2011

### **GMBU W-7-9-17**

**Waiting on Cement** 

**Date:** 7/12/2011

Ross #26 at 325. Days Since Spud - yield. Returned 4 bbls to pit, bump plug to 320 psi, BLM and State were notified of spud via email. - On 7/8/11 Ross #26 spud and drilled 325' of 12 1/4" hole, P/U and run 7 jts of 8 5/8" casing set - 326.62'KB. On 7/12/11 cement w/BJ w/160 sks of class G+2%kcl+.25#CF mixed @ 15.8ppg and 1.17

Daily Cost: \$0

**Cumulative Cost:** \$65,260

**GMBU W-7-9-17** 

Rigging down

**Date:** 7/20/2011

NDSI #3 at 325. 2 Days Since Spud - Rig down

Daily Cost: \$0

**Cumulative Cost:** \$65,260

## GMBU W-7-9-17

## Drill 7 7/8" hole with fresh water

**Date:** 7/21/2011

NDSI #3 at 1180. 1 Days Since Spud - R/U B&C quicktest Test Kelly,safty valve,choke manifold,Pipe and blind rams @ 2000 PSI - Tear down move rig from G-18-9-17 to the W-7-9-17 - Surface csg @ 1500 PSI - test good - Tag @ 278' Drill 7 7/8" hole F/278' - 990', w/ 20 WOB, 165 RPM, 340 GPM,ROP 101 - Install rotating rubber and dry bushings - Drill 7 7/8" hole F/990' -1180 ', w/ 20 WOB, 160 RPM, 340 GPM,ROP 95 - P/U Sec7 7/8" PDC FX65M bit, .33 1.5° 7/8 lobe Hunting Mud motor,Pay Zone Directional tools

Daily Cost: \$0

**Cumulative Cost:** \$107,977

### **GMBU W-7-9-17**

### Drill 7 7/8" hole with fresh water

**Date:** 7/22/2011

NDSI #3 at 3250. 2 Days Since Spud - Saftey stand down w/Ray Hererra all work stop.

Discused saftey topics. - Drill 7 7/8" hole from 1180' to 1808'

WOB/20,TGPM/400,RPM/48,ROP/104 - Drill 7 7/8" hole from 1808' to 3250'

WOB/20,TGPM/400,RPM/48,ROP/82.4

Daily Cost: \$0

**Cumulative Cost:** \$154,310

### **GMBU W-7-9-17**

# Drill 7 7/8" hole with fresh water

**Date:** 7/23/2011

NDSI #3 at 4720. 3 Days Since Spud - Drill 7 7/8" hole from 3828' to 4720' WOB/20,TGPM/400,RPM/48,ROP/55.74 - Drill 7 7/8" hole from 3250' to 3828'

WOB/20,TGPM/400,RPM/48,ROP/82.4 - Rig Service

Daily Cost: \$0

Cumulative Cost: \$196,300

### **GMBU W-7-9-17**

**Circulate & Condition Hole** 

**Date:** 7/24/2011

NDSI #3 at 6112. 4 Days Since Spud - Drill 7 7/8" hole from 5151' to 6112' WOB/20,TGPM/400,RPM/48,ROP/64 - Circulate for logs - Drill 7 7/8" hole from 4720' to 5152' WOB/20,TGPM/400,RPM/48,ROP/55.74 - Rig service

Daily Cost: \$0

**Cumulative Cost:** \$227,922

### **GMBU W-7-9-17**

### **Wait on Completion**

**Date:** 7/25/2011

NDSI #3 at 6112. 5 Days Since Spud - Rig up and run casing 140jts plus 1 mandril 5.5, 15.5# casing set @ 6090.46 'KB - Change rams and test 200psi for 10min. - Rig up loggers and log; Standard triple combo with PSI - LDDP & BHA - Circulate with rig pump - 426sks tail; 50:50+3%KCL+.5%EC-1+.25#CF+.05#SF-6L - Clean Mud Tanks - Release rig @ 2:00am 7/25/11 - Cement with BJ 260sks lead; PLII+3%KCL+5#CF+2#KOL.5SMS+FP+SF **Finalized** 

Daily Cost: \$0

Cumulative Cost: \$361,295

**Pertinent Files: Go to File List**